

Annex A: Bill of Quantities

Name of Project: CONSTRUCTION OF KSU-BULANA0 CAMPUS GATE 2-PHASE I

ITEM NO.	DESCRIPTION	QTY	UNIT	Unit Price (in Pesos)	Total Cost (in Pesos)
B.3	PERMITS AND CLEARANCES	1.00	lumpsum		
B.5	PROJECT BILLBOARD	1.00	set		
B.7	OCCUPATIONAL SAFETY AND HEALTH PROGRAM	1.00	lumpsum		
800(2)	CLEARING, GRUBBING AND LAY-OUT	1.00	lumpsum		
800(3)a1	CLEARING AND GRUBBING (INDIVIDUAL REMOVAL OF TREES, 100-150mm Ø)	1.00	each		
801(1)	REMOVAL OF STRUCTURES AND OBSTRUCTION (COVERED PATHWALK FOOTING & ROOFING)	1.00	lumpsum		
801(3)a	REMOVAL OF STRUCTURES AND OBSTRUCTION (CONCRETE)	24.40	sq.m.		
803(1)a	STRUCTURE EXCAVATION (Common soil)	22.79	cu. m.		
804(1)a	EMBANKMENT FROM STRUCTURE EXCAVATION	11.51	cu. m.		
804(4)	GRAVEL FILL (GRAVEL BEDDING)	1.03	cu. m.		
900(1)c1	STRUCTURAL CONCRETE (class A)	15.11	cu. m.		
902(1)a1	REINFORCING STEEL BARS (Grade40, deformed)	882.76	kgs.		
902(1)a2	REINFORCING STEEL BARS (Grade 60, Deformed)	1174.74	kgs.		
903(2)	FORMS & FALSEWORKS	123.76	sq.m.		
1046(2)	CHB NON-LOAD BEARING 6" (RSB included)	14.37	sq.m.		
1053(1)	STEEL TUBULAR MOULDINGS (GATE)	190.13	ln.m.		
1100	CONDUITS, BOXES & FITTINGS	1.00	Lumpsum		
TOTAL BID AMOUNT (in figures): Php					
TOTAL BID AMOUNT (in words): Pesos					

Note: The Bill of Quantities (BOQ) contains the following parts:
a. BOQ for each Part of the Contract.
b. Summary of Bid Prices for all Parts of the Contract.

Project Duration: **69 calendar days**

Submitted by:

Name and Signature of Bidder's Representative: _____

Position: _____

Name of Bidder: _____

Date: _____