



Annex A: Bill of Quantities

Name of Project: **IMPROVEMENT OF GOATERY AND A.I. LABORATORY – KSU RIZAL CAMPUS**

ITEM NO.	DESCRIPTION	QTY	UNIT	Unit Price (in Pesos)	Total Cost (in Pesos)
B.5	PROJECT BILLBOARD	1.00	set		
B.7	OCCUPATIONAL SAFETY AND HEALTH PROGRAM	1.00	lumpsum		
803(1)a	STRUCTURE EXCAVATION (Common soil)	5.40	cu. m.		
804(1)a	EMBANKMENT FROM STRUCTURE EXCAVATION	1.80	cu. m.		
804(4)	GRAVEL FILL (GRAVEL BEDDING)	0.68	cu. m.		
900(1)c3	STRUCTURAL CONCRETE WORKS (Wall Footing)	2.70	cu. m.		
902(1)a1	REINFORCING STEEL BARS (Grade 40, deformed)	111.06	kgs.		
1002(8)	PLUMBING FIXTURES AND FITTINGS	1.00	Ls		
1003(1)a1	CEILING (4.5MM FIBER CEMENT BOARD ON METAL FRAME CEILING)	22.15	sq.m		
1004(2)a	LOCKSET	2.00	sets		
1004(2)g	HINGE	3.00	sets		
1010(2)b	WOOD PANEL DOOR	1.47	sq.m		
1013(1)	CORRUGATED METAL SHEETS	132.23	sq.m.		
1018(1)	GLAZED TILES	10.15	sq.m		
1018(2)	UNGLAZED TILES	2.33	sq.m		
1027(1)	CEMENT PLASTER FINISH	72.00	sq.m.		
1032(1)a	PAINTING WORKS (MASONRY/CONCRETE)	87.58	sq.m		



Republic of the Philippines
KALINGA STATE UNIVERSITY
National Highway, Purok 6, Bulanao, Tabuk City, Kalinga
Bids and Awards Committee

1032(1)b	PAINTING WORKS (CEILING)	22.15	sq.m		
1046(2)	CHB NON LOAD BEARING 4" (RSB included)	45.00	sq.m.		
1047(1)	STRUCTURAL STEEL	1.00	lumpsum		
1202 (24) a3	FIRE EXTINGUISHER (10lbs, CO2/ HCFC123 with bracket)	2.00	set/s		
SPL I	MISCELLANEOUS WORKS	1.00	lumpsum		
SPL-II	FLOORING SYSTEM	19.76	sq.m		
				TOTAL BID AMOUNT (in figures): Php	
TOTAL BID AMOUNT (in words): Pesos					

Note: The Bill of Quantities (BOQ) contains the following parts:
a. BOQ for each Part of the Contract.
b. Summary of Bid Prices for all Parts of the Contract.

Project Duration: **55 Calendar days**

Submitted by:

Name and Signature of Bidder's Representative: _____

Position: _____

Name of Bidder: _____

Date: _____