



## Annex B\_Scope of Works

**Name of Project: Repainting of Dagupan Campus Covered Pathwalk and Façade of CLA Building including Fixing Damaged Pipes**

ITEM No.	ITEMS OF WORK	QTY	UNIT	SCOPE OF WORKS
800	CLEARING AND GRUBBING	235.40	sq.m	-cleaning of the following to be painted façade of CLA Building roof of pathway -specs are as follows whole exterior wall, 7400x25000 G.I. corrugated sheet, 2700x1800 steel brush minor tools
801(1)	REMOVAL OF STRUCTURES AND OBSTRUCTION	1.00	lumpsum	- includes chiseling of concrete wall plaster -removal of damaged pipe -specs are as follows minor tools
1002 (8)	PLUMBING FIXTURES AND FITTINGS	1.00	lumpsum	- replacing the damaged pipe -specs are as follows 15mm pvc pipe Teflon Tape Solvent Faucet 15mm Pvc Pipe Tee 15mm Pvc Pipe elbow 90°
1027	CEMENT PLASTER FINISH	0.15	sq.m	- filling up the chiseled concrete wall plaster -specs are as follows cement Sand
1032(1) a	PAINTING WORKS (masonry/concrete)	185.00	sq.m	- covers all exterior façade wall of CLA Building -specs are as follows: Paint, latex, (mint green, white, baguio green) Paint, latex, flat white Masonry putty Sandpaper Rollerbrush with pan Roller brush foam Paint Brush x 75 Paint Brush x 50 Paint (1 set for Logo and Lettering) - includes the letterings of KALINGA STATE UNIVERSITY -details are specified in the plans, paints to be verified first before application - three coats are to be applied on the concrete walls
1032(1) c	PAINTING WORKS (steel)	54.00	sq.m	-covers the roof of pathwalk at the main entrance -specs are as follows Paint, Acrylic, Baguio green Sandpaper (rough) Rollerbrush with pan Roller brush foam Paint Brush x 75 Paint Brush x 50 -details are specified in the plans, paints to be verified first before application -two coats are to be applied on the roof area