



Annex B: Scope of Works

*Name of Project:* **IMPROVEMENT OF POULTRY HOUSING-KSU BULANA O  
CAMPUS**

| ITEM No.  | ITEMS OF WORK                          | QTY    | UNIT    | SCOPE OF WORKS   |
|-----------|--|--------|---------|--|
| B.7       | OCCUPATIONAL SAFETY AND HEALTH PROGRAM | 1.00   | lumpsum | -covers the provision of safety officer on-site and PPEs for the workers<br><br>-specs are as follows<br>Safety Officer<br>safety gloves<br>safety helmet<br>safety shoes  |
| 801       | REMOVAL OF STRUCTURES AND OBSTRUCTION  | 1.00   | lumpsum | -covers the removal of existing structures and obstruction:<br><br>roof<br>any existing obstructions<br>Minor Tools(10%)   |
| 1003 (17) | CARPENTRY AND JOINERY WORKS            | 1.00   | lumpsum | -item covers the installation of additional wooden wall frame and door, replacement of rotted/ termite infested wood frames of the floor, wall frames, and roof frames<br>-specs are as follows:<br><br>Minor tools<br>Good Lumber, 2"x6", Well Seasoned Wood<br>Good Lumber, 2"x3", Well Seasoned Wood<br>Good Lumber, 2"x2", Well Seasoned Wood<br>CWN assorted<br>Door Hinge 3"x3"2mm, screws included<br>3" Safety HASP Latch Lock with Screws<br>Podlock<br>-refer to plans for details |
| 1013(1)   | CORRUGATED METAL ROOFING               | 184.80 | Sq.m    | -item covers the installation of corrugated metal sheets<br><br>-specs are as follows:<br><br>H-frame/GI pipe scaffolds<br>Minor tools (10% Labor)<br>Corrugated metal roofing, gauge 26<br>Ordinary Ridge Roll, GA 24 (0.701mm) X 2.44m<br>Umbrella Nail  |
| 1100      | ELECTRICAL                             | 1.00   | lumpsum | -item covers the installation of conduits, boxes and fittings as specified in the plans<br><br>-specs are as follows:<br>PDX wire #14 (40m)  |



Republic of the Philippines  
**KALINGA STATE UNIVERSITY**  
 National Highway, Purok 6, Bulanao, Tabuk City, Kalinga  
*Bids and Awards Committee*

|         |                          |        |         |  |
|---------|--------------------------|--------|---------|--|
|         |                          |        |         | Triplex switch surface type<br>Utility Box (orange)<br>Junction Box<br>Sealant Sachet<br>Insulated staple box<br>LED T8 WP outdoor fixture<br>(1x36W)<br>Flood Light 35W daylight 2500lm<br>15AT KSB circuit breaker   |
| SPL-I   | ALUMINUM FOAM INSULATION | 184.80 | Sq.m    | -item covers the installation of aluminum foam under the roofing panels<br><br>-specs are as follows:<br><br>Minor tools (10% Labor)<br>10mm thk. Double sided<br>Aluminum foam insulation (50m-roll)<br>Chicken Wire Mesh, 25x25mm holes, 4ft height, 30 yards length<br><br>-refer to plans for details  |
| SPL-II  | CHICKEN MESH ENCLOSURE   | 160.23 | Sq.m    | -item covers the installation of chicken mesh enclosing the poultry walls<br><br>-specs are as follows:<br><br>Minor tools (10% Labor)<br>Chicken mesh, plastic green, 1/2 inch hole, 4ft height, 30yard length<br>Waterproof Tarpauline Blue (tolda)<br>U-Shaped Nail<br>No. 18 G.I Tie wire  |
| SPL-III | MISCELLANEOUS WORKS      | 1.00   | lumpsum | -item covers the installation of miscellaneous items, installation and replacement of damaged plastic floor mattings, installataion of access ladder at the water feeder source<br><br>-specs are as follows:<br><br>Plastic Matting, Heavy Duty, 600x600mm<br>Angle Bar, 50mm x 50mm, 5mm thick, 6m<br>16mmØ RSB, G40<br>Welding Rod<br>No. 18 G.I Tie wire |