



Republic of the Philippines
KALINGA STATE UNIVERSITY
 Tabuk City, Kalinga 3800
Bids and Awards Committee



Annex B: Scope of Works

Name of Project: ELECTRIFICATION OF KSU RIZAL GOAT FARM

ITEMS NO.	ITEMS OF WORK	QTY	UNIT	SCOPE OF WORKS
SPL I	Electrical Post	1.00	Ls	-covers installation of electric posts including all accessories specs are as follows: 30' Steel Post including all necessary accessories Secondary Rack Two Spool Assembly Secondary Rack Single Spool Assembly Welding Rod Metal Screw 3/4" x 150mm dia. Metal Washer 150mm dia. Hole #14 Tie Wire Split Bolt Connector Kilowatt Meter with Base Meter Box, 13"X10"X8" Fabricated GI Steel Post: Reinforcing Steel Bars (16mm dia.) Portland Cement Washed Sand Crushed Gravel (G1) GI Pipe 4" x 6m #16 Tie Wire 1/2" THK Phenolic Board
B.3	Permits and Clearances	1.00	Ls	-covers processing of KAELCO permit specs are as follows: Permits and Clearances covers processing of the following: KAELCO Processing Fee Building Permit