



Annex B: Scope of Works

**Name of Project: REPAIR OF HIGH SCHOOL BUILDING (ROOFING, CEILING AND DOWNSPOUT)**

ITEM No.	ITEMS OF WORK	QTY	UNIT	SCOPE OF WORKS
B.7	OCCUPATIONAL SAFETY AND HEALTH PROGRAM	1.00	Ls	- covers the provision of safety officer on site and PPE's for the workers specs are as follows: safety gloves safety helmet safety shoes
101(1)	REMOVAL OF STRUCTURES AND OBSTRUCTIONS	1.00	Ls	- covers the removal of roofing sheets, gutter, flashing and downspouts specs are as follows: Power Tool Minor Tools (10% of Labor) Tile Cutter Disk *Removal of existing roofing sheets *Removal of existing gutter *Removal of existing downspouts
1001(9)	STORM DRAINAGE AND DOWNSPOUT	1.00	Ls	- covers the installation of storm drainage and downspout as indicated in the plan  specs are as follows: Set of plumbing tools PVC Pipe, 3" Ø x 3m, S-1000 Elbow, 75mm dia. x 90 deg. Bend  PVC Clamp Roof Drain (Dome-type strainer) PVC Solvent, 100cc <b>NOTE: REFER TO THE PLAN FOR DETAILS</b>
1003(1)b1	CEILING	103.68	sq.m	- covers the replacement of dilapidated ceiling at second floor as indicated in the plan specs are as follows: Minor tools (10% of Labor) Power Tools H-Frame, G.I. Pipe Scaffolds Fiber Cement Board, 1.2m x 2.4m x 4.5mm THK 2" x 2" x 8' Good Lumber Blind Rivets, 1/8 x 1/2 (1000pcs) 1" CW Nails <b>NOTE: REFER TO THE PLAN FOR DETAILS</b>
1003(8)	FLOORING (WOOD)	64.56	bd.ft	- covers the replacement of dilapidated wood planks as indicated in the plan  specs are as follows: Minor tools (10% of Labor) 1" x 2" x 8' Hard Wood Plank 1" CW Nails <b>NOTE: REFER TO THE PLAN FOR DETAILS</b>
1013(2)a	FABRICATED METAL ROOFING AND ACCESSORY (RIDGE ROLL), GA 24	66.40	ln.m	- covers installation of ridge roll as indicated in the plan specs are as follows: Minor tools (10% of Labor) Power Tools



Republic of the Philippines  
**KALINGA STATE UNIVERSITY**  
 Tabuk City, Kalinga 3800  
*Bids and Awards Committee*



				Pre-painted Ridge Roll GA 24 (0.701mm) x 2.44m (VERIFY COLOR) Blind Rivets (5 3/2 x 1/2") <b>NOTE: REFER TO THE PLAN FOR DETAILS</b>
1013(2)c	<b>FABRICATED METAL ROOFING AND ACCESSORY (GUTTER), GA 24</b>	132.80	In.m	- covers installation of gutter as indicated in the plan  specs are as follows: Minor tools (10% of Labor) Power Tools Pre-painted Spanish Gutter 24", GA 24 (0.701mm) x 2.44m (VERIFY COLOR) 12" x 1" Plain GI Strap Blind Rivets (5 3/2 x 1/2") <b>NOTE: REFER TO THE PLAN FOR DETAILS</b>
1013(2)f	<b>FABRICATED METAL ROOFING AND ACCESSORY (COUNTER FLASHING GUTTER), GA 24</b>	23.00	In.m	- covers installation of flashing as indicated in the plan  specs are as follows: Minor tools (10% of Labor) Power Tools Pre-painted Counter Flashing Gutter GA 24 (0.701mm) x 2.44m (VERIFY COLOR) Blind Rivets (5 3/2 x 1/2") <b>NOTE: REFER TO THE PLAN FOR DETAILS</b>
1014(1)b1	<b>PRE-PAINTED METAL SHEETS (CORRUGATED, LONG SPAN, 0.5MM THK)</b>	763.60	sq.m	- covers installation of roofing as indicated in the plan  specs are as follows: Minor tools (10% of Labor) Power Tools Pre-painted Corrugated Roofing Sheet (Gauge 26, 1000mm Width x 12') Pre-painted Corrugated Roofing Sheet (Gauge 26, 1000mm Width x 10') Tek screw, 12x35mm (500pcs) <b>NOTE: REFER TO THE PLAN FOR DETAILS</b>
1032(1)b	<b>PAINTING WORKS (Ceiling)</b>	103.68	sq.m	- covers painting of ceiling  specs are as follows: Minor tools (10% of Labor) H-Frame, G.I. Pipe Scaffolds Latex Flat White Latex Semi-Gloss White Plasolux Glazing Putty Paint Thinner Roller brush with pan Roller Brush foam Paint Brush x 100 <b>NOTE: REFER TO THE PLAN FOR DETAILS</b>
1032(1)c	<b>PAINTING WORKS (Steel)</b>	216.00	sq.m	- covers painting of existing steel frames  specs are as follows: Minor tools (10% of Labor) H-Frame, G.I. Pipe Scaffolds Red Oxide Primer Rust converter Roller brush with pan Paint Brush x 100 <b>NOTE: REFER TO THE PLAN FOR DETAILS</b>