



Annex B: Scope of Works

**Name of Project: ROOF REPLACEMENT AND ADDITIONAL MATERIALS OF KSU
 POULTRY- BULANA O CAMPUS**

ITEM No.	ITEMS OF WORK	QTY	UNIT	SCOPE OF WORKS
B.7	OCCUPATIONAL SAFETY AND HEALTH PROGRAM	1.00	lumpsum	-covers the provision of safety officer on-site and PPEs for the workers -specs are as follows Safety Officer safety gloves safety helmet safety shoes
801	REMOVAL OF STRUCTURES AND OBSTRUCTION	1.00	lumpsum	-covers the removal of existing structures and obstruction: roof any existing obstructions Minor Tools(10%)
1003 (9)	CARPENTRY AND JOINERY WORKS (Wall Frame)	14.00	pcs	- item covers the installation of additional wooden wall frame and door as specified in the plans -specs are as follows: Minor tools Good Lumber, 2"x3", Well Seasoned Wood Good Lumber, 2"x2", Well Seasoned Wood CWN 4" Door Hinge 3"x3"2mm, screws included 3" Safety HASP Latch Lock with Screws Podlock -refer to plans for details
1013(1)	CORRUGATED METAL ROOFING	184.80	sq.m.	-item covers the installation of corrugated metal sheets -specs are as follows: H-frame/GI pipe scaffolds Minor tools (10% Labor) Corrugated metal roofing, gauge 26 Ordinary Ridge Roll, GA 24 (0.701mm) X 2.44m Umbrella Nail
1100	ELECTRICAL	1.00	lumpsum	-item covers the installation of conduits, boxes and fittings -specs are as follows: PDX wire #14 (40m) Triplex switch surface tupe Utility Box (orange) Junction Box Sealant Sachet Insulated staple box LED T8 WP outdoor fixture (1x36W) Flood Light 35W daylight 2500lm 15AT KSB circuit breaker
SPL-I	ALUMINUM FOAM INSULATION	184.80	sq.m	-item covers the installation of aluminum foam under the roofing panels -specs are as follows: Minor tools (10% Labor) 10mm thk. Double sided Aluminum foam insulation (50m-roll) Chicken Wire Mesh, 25x25mm holes, 4ft height, 30 yards length -refer to plans for details



Republic of the Philippines
KALINGA STATE UNIVERSITY
National Highway, Purok 6, Bulanao, Tabuk City, Kalinga
Bids and Awards Committee

SPL-II	CHICKEN MESH ENCLOSURE	160.23	sq.m	-item covers the installation of chicken mesh enclosing the poultry walls -specs are as follows: Minor tools (10% Labor) Chicken mesh, plastic green, 1/2 inch hole, 4ft height, 30yard length Waterproof Tarpauline Blue (tolda) U-Shaped Nail No. 18 G.I Tie wire
---------------	-------------------------------	--------	------	---