



## Annex C: Scope of Works

ITEMS NO.	ITEMS OF WORK	QTY	UNIT	SCOPE OF WORKS
B.1	PROVISION FOR SAFETY & HEALTH	1.00	Ls	-covers the safety protective equipment of all workers specs are as follows: safety gloves safety shoes safety helmets
800(1)	CLEARING, GRUBBING AND LAY-OUT	1.00	Ls	-covers clearing and lay-outing of the area
803(1)	STRUCTURE EXCAVATION	6.05	cu.m.	-covers the excavation for footings as specified in the plan
804(1)a	EMBANKMENT FROM STRUCTURE EXCAVATION	1.35	cu.m.	-covers embankment from excavation
804(4)	GRAVEL BEDDING	0.31	cu.m.	-covers spreading and compaction of 2" THK gravel bedding for all footings specs are as follows: Gravel (G1)
900(1)	STRUCTURAL CONCRETE	2.05	cu.m.	-covers concrete works for all footings and columns as specified in the plan specs are as follows: Portland Cement Washed Sand Gravel 1"
902(1)a1	REINFORCING STEEL BARS, DEFORMED, GRADE 40	252.39	kgs.	-covers reinforcing steel bars for all footings and columns as specified in the plan specs are as follows: Grade 40 RSB (12mm and 10mm dia) no. 16 GI tie wire
903(2)	FORMS AND FALSEWORKS	43.68	sq.m	-covers the forms and falseworks for all footings and columns as specified in the plan specs are as follows: 1/2" thk. Phenolic Board (2-3 Uses) Good Lumber common wire nails (assorted)
1002(3)a1-a	GALVANIZED IRON PIPE SCHEDULE 40 (20MM DIA)	45.00	pcs	-covers fabrication and installation of 3/4" THK GI Pipe as specified in the plan specs are as follows: GI Pipe - 3/4" dia. SCH 40 Welding Rod Tekscrew x55



Republic of the Philippines  
**KALINGA STATE UNIVERSITY**  
 Tabuk City, Kalinga 3800  
*Bids and Awards Committee*



1002(3)a2	GALVANIZED IRON PIPE SCHEDULE 40 (25MM DIA)	<b>30.00</b>	<b>pcs</b>	-covers fabrication and installation of 1" THK GI Pipe as specified in the plan specs are as follows: GI PIPE- 1" dia. SCHED 40 Welding Rod Tekscrew x 55
1002(3)a5	GALVANIZED IRON PIPE SCHEDULE 40 (50MM DIA)	<b>55.00</b>	<b>pcs</b>	-covers fabrication and installation of 2" THK GI Pipe as specified in the plan specs are as follows: GI PIPE- 2" dia. SCHED 40 Welding Rod Tekscrew x 55
1002(3)a7	GALVANIZED IRON PIPE SCHEDULE 40 (75MM DIA)	<b>17.00</b>	<b>pcs</b>	-covers fabrication and installation of 3" THK GI Pipe as specified in the plan specs are as follows: GI PIPE- 3" dia. SCHED 40 Welding Rod Tekscrew x 55
1046(2)	CHB NON-LOAD BEARING	<b>49.66</b>	<b>sq. m.</b>	-covers the installation of CHB on all sides as specified in the plan specs are as follows: 4" CHB washed sand portland cement Reinforcing steel bars (Grade 40) GI Tie Wire