



Annex C: Scope of Works

Name of Project: INSTALLATION OF ROOFING AT CENTRAL LABORATORY AT KSU-BULANAO CAMPUS

ITEM No.	ITEMS OF WORK	QTY	UNIT	SCOPE OF WORKS
1047	METAL STRUCTURES	1.00	lumpsum	-covers installation of the following at Central Laboratory Building 2 x 4 Channel Bar Standard Heavy Duty 2 x 2 Angle Bar (Cross Bar/ Cleats) 2x 3 G.I. C-Purlins 2 x 10 G.I. Facia 2 x 3/16 Flat Bar 12mm Sag Rod Metal Primers Welding Rods Paint Thinner Paint Brush Cut Off Disk Cutting Wheel 14" MS Plate 10mm Dyna Bolt 3/4 x 3 -refer to plans for details
1014(1)b2	PREPAINTED METAL SHEETS (RIBB TYPE)	451.00	sq.m	-covers installation of the following at Central Laboratory Building Rib Type 0.50mm thick Ridge Roll 24" x 0.50mm thick x 8' Valley Gutter 24" x 0.50mm thick x 8' Gutter 24" x 0.50mm thick x 8' Side End Flashing 24" x 0.50mm thick x 8' Wall Flashing 12" x 0.50 mm thick Facia Cover 12" x 0.40mm thick J-Bolt Blind Rivets Vulca Seal -refer to plans for details