



Republic of the Philippines  
**KALINGA STATE UNIVERSITY**  
 Bulanao, Tabuk City, Kalinga

PROJECT: REPAIR OF DAGUPAN LIBRARY  
 LOCATION: KSU Dagupan Campus, Tabuk City, Kalinga

ITEM No.	ITEMS OF WORK	QTY	UNIT	SCOPE OF WORKS
801	Removal of structures and obstructions(wall)	45.60	sq.m	-chiselling of wall for the construction of corridor at roof deck
				-chiselling of one door at roof deck
				-chiselling of wall for the construction of library room at ground floor
1047	Metal Structures(Canopy)	49.50	sq.m	-dismantling the tubular purlin to be replaced by a C-purlins
				at grid J(1-9) and at grid 4 to 9
				-replacing the covering polycarbonate sheet to rib type roofing
				at grid J(1-9) and at grid 4 to 9
				Specs are as follows:
				Rib Type # 40
				C purlins x 6m(1.5mmx 50mmx75mm)
				ordinary side flashing
				tekscrew x55(steel)
				blind rivets
				silicon sealant
				silicon gun
				wall flashing
				welding rod
1032(1)a2	PAINTING(WOOD)	328.81	sq.m	-covers items @ ceiling, perimeter wall(0.60m),perimeter wall lining(0.25m)
				room partition, corridor partition at the roof deck
				Specs are as follows:
				QDE Flat White
				QDE Gloss White
				QDE Choco Brown
				Oil Based Rawsienna Tinting Color 1/4 lit.
				Sand Paper # 200
				Paint Thinner
				Roller Brush Medium Size faom
				Roller Paint Brush M/S w/ pan
				Paint Brush x 100
				Paint Brush x 75
				Paint Brush x 50
1013	TINNERY	1.00	lot	-covers items @ roofing at roof deck
				Specs are as follows:
				vulcaseal 1/4 liter
1010(2)b	WOODEN DOORS	6.72	sq.m	-installation of doors at roof deck (see plan for location)
				4 sets of doors(0.80mx2.1m)
				(0.8mx 2.10m)35mm thk wood panel door with 6mm thk panel on 2"x 6"
				wooden door jamb with complete hardware
1027	CEMENT PLASTER FINISH	13.89	sq.m	-covers items @ walls roof deck
				-covers items @ walls specifically ground floor for the chiselled walls
				Specs are as follows:
				sand
				cement
1032(1)a1	PAINTING(MASONRY/CONCRETE)	481.85	sq.m	-covers items @ walls 1m height for two sides at roof deck
				-covers items @ walls specifically the side of chiselled walls at groun floor
				Specs are as follows:
				Permacoat Flat White
				Permacoat Gloss White
				Oil Based Rawsienna Tinting Color 1/4 lit.
				Sand Paper # 200

ITEM No.	ITEMS OF WORK	QTY	UNIT	SCOPE OF WORKS
				laquer thinner
				Roller Paint Brush Medium foam
				Roller Paint Brush M/S w/ pan
				Paint Brush x 100
				Paint Brush x 75
				Paint Brush x 50
				Permacoat Choco brown
1100	ELECTRICAL	62.00	outlet	-installation of electrical fixtures at roof deck and ground floor
				Specs are as follows:
				Lighting
				Ground floor
				1. 2.0mm sq THHN wire (white and black)
				2. 3/4" pvc white mouldex wire cover
				3. 2x18W LED flourescent lamp 1.2m surface mounted Daylight with aluminum reflector
				4. Mica Tube 3/4" dia
				5. Three gang switch (wide series)
				6. Surface mounted utility box
				7. Splice box
				8. Concrete Black Screw
				Deck Floor
				1. 2.0mm sq THHN wire (white and black)
				2. 3/4" pvc white mouldex wire cover
				3. 2x18W LED flourescent lamp 1.2m surface mounted Daylight with aluminum reflector
				4. Mica Tube 3/4" dia
				5. Three gang switch (wide series)
				6. Two gang switch (wide series)
				6. Surface mounted utility box
				7. Splice box
				8. Concrete Black Screw
				Power
				Ground floor
				1. 3.5mm sq THHN wire (white and black)
				2. 1" pvc white mouldex wire cover
				3. Convenience outlet, 16A, Duplex, 3prong, 250V
				4. Mica Tube 3/4" dia
				5. Surface mounted utility box
				6. Concrete Black Screw
				Deck Floor
				1. 3.5mm sq THHN wire (white and black)
				2. 1" pvc white mouldex wire cover
				3. Convenience outlet, 16A, Duplex, 3prong, 250V
				4. Mica Tube 3/4" dia
				5. Surface mounted utility box
				6. Concrete Black Screw
				Appliance
				Ground floor
				1. 5.5mm sq THHN wire (white and black)
				2. 1.5HP inverter Split-type Air Conditioner (White)
				3. 1" pvc white mouldex wire cover
				4. Convenience outlet, 16A, Duplex, 3prong, 250V
				5. Special purpose aircon outlet 3prong, 250V
				6. Mica Tube 3/4" dia
				7. Surface mounted utility box
				8. Concrete Black Screw
				9. 25mm dia uPVC pipe
				10. Octagonal Junction Box
				11. Ceiling Fan , orbit type, 16" diameter, steel blade
				12. 3.5mm sq THHN wire

ITEM No.	ITEMS OF WORK	QTY	UNIT	SCOPE OF WORKS
				Protection
				1. 12 branches Panel Board
				2. 2P-90AT Circuit Breaker bolt-on type
				3. 2P-30AT Circuit Breaker bolt-on type
				4. 2P-20AT Circuit Breaker Bolt-on type
				4. 2P-15AT Circuit Breaker Bolt-on type
				5. NEMA 3R Circuit breaker enclosure
				6. 22mm sq THHN wire
				7. Secondary Rack
1030(d4)	ACOUSTICAL CEILING	57.60	sq.m	-covers item @ ceiling roof deck
				Specs are as follows:
				Marine Plywood 1/4" x 1.2 x 2.4
				CW nail x 25
				Stickwell glue 1/4 liter
				Scaffolding lumber 2"x2"x3.6m
1003(a1)	WALL CARPENTRY ND JOINERY WORKS	73.00	pcs	-covers item @ wall partition at roof deck
				Specs are as follows:
				Marine Plywood 1/4" x 1.2 x 2.4
				2"x2"x3.6m good lumber
				#1 CW Nails
				#2 1/2 CW Nails
1009	Jalousie Window(Analock Frame)	3.00	sq.m	-installation of window at roof deck
				5 sets of 2.0mx 1.20m window
				Specs are as follows:
				analock framed jalousie window(2.0x1.20m)
				note: with all accessories
SPL - V	PROJECT BILLBOARD	1.00	piece	Specs are as follows:
				1/4" x 4' x 8' marine plywood
				good lumber
				tarpauline (4' x 8')
				CWN (assorted)

Prepared by:

**JORDAN ESTELONG**  
KSU PROJECT IN-CHARGE

Checked by:

Recommending Approval:

**Engr. JAYBHOY BITAGA**  
Chairman, INFRA DEPT.

**Engr. RHONJHON R. GARMING**  
Director for Planning and Strategy

Approved:

**EDUARDO T. BAGTANG, CPA, DBM**  
SUC President III