



SCOPE OF WORK

Name of Project : ENGINEERING BUILDING REPAIR		Location : KSU BULANAo CAMPUS, BULANAo, TABUK CITY	
ITEM	ITEMS OF WORK TO BE DONE	UNIT	SCOPE OF WORKS
1018(2)	CERAMIC TILES	sq. m.	2.00
			- Chiselling Floor Tiles (200mmx200mm) @ 1st Floor Right Wing Cr
			- Installation of Mariwasa Floor Tiles Non Skid(200mmx200mm) @ 1st Floor Right Wing Cr
			-PVC Tile Trim @ 1st Floor Right Wing
			-Bostik Tile Grout
1010(2)b	WOODEN DOORS	sq. m.	3.00
			-2 sets (0.7mx2.1m)hardwood Panel Doors @ 1st Floor Left Wing Cr
			-Enamel Paint Choco brown, 2 sets of door
			-Cilindrical DoorKnob @ 1st Floor Left Wing Cr, 2 Doorknobs @2nd Floor Right Wing Cr, 1 Doorknob @3rd Floor Right Wing Cr, 2 doorknobs @4th Floor Right wing Cr, 1 Doorknob @ Cr Loose Pin Hinges, 3 Pin Hinges @Room ETB 205, 1 Doorknob @Room ETB 204, 1 Doorknob @Room ETB 203, 1 Doorknob @3rd Floor Room Elab, 1 Doorknob @Room ETB 304, 2 Doorknobs @Room ETB 207, 1 Doorknob @CR beside ETB 207, 1 Doorknob @Infrastructure Room, 1 Doorknob @Room ETB 208, 1 Doorknob Door covered @ Room ETB 203 Ordinary Plywood 1/4" x 1.2 x 2.4
1002.2.2	WATER SUPPLY PIPES AND FITTINGS	ln.m	6.00
			-@ 1st Floor Right Wing Cr, 2 Blue Pipe 200mm dia.x3m -@ 1st Floor Rightwing Cr, 2 Pvc Tee 200mm dia -@ Cr 16 pieces PVC elbow 200mm x 90deg
1021(3)	FLOOR TOPPING (PLAIN)	cu.m.	3.58
			-Chiselling and removal of obstruction, Location @Right wing Tank @Left wing Tank @Slab at Roof -Floor topping, Location @Right wing Tank @Left wing Tank @Slab at Roof @Room Grid D(13-15) E(13-15)
1002.2.5	PLUMBING FIXTURES AND FITTINGS	Lot	1.00
			-Urinal P-trap @ 1st Floor Left Wing, 3 pieces -Flexible Hose with angle valve @ 1st Floor Left Wing Cr, 4 pieces @ 2nd Floor Left Wing Cr, 2 pieces for water closet @ 2nd Floor Left Wing Cr, 2 pieces for lavatory @ 3rd Floor Left Wing Cr, 1 piece @ 2nd Floor Right Wing Cr, 2 pieces for water closet -Lavatory Faucet @ 1st Floor Left Wing Cr, 3 pieces -Urinal Valve assembly @ 3rd Floor Right Wing Cr, 1 piece -Floor Drain 100x100 @ 1st Floor Left Wing Cr, 2 pieces -Ordinary Faucet @ 1st Floor Left Wing Cr, 2 pieces -Lavatory P-trap(2 inches) @ 1st Floor Right Wing Cr, 1 piece -Concrete Epoxy
1012(2)	GLASS AND GLAZING	sq.m.	14.00
			-Smoke Glass 35cmx35cm, 2 pieces @ 1st Floor Right Wing , 1 piece @ 2nd Floor Right Wing , 1 piece -Clear Glass 30cmx45cm, 46 pieces @ 3 pcs Room ETB 201, 2 pcs Room ETB 205, 7 pcs Room ETB 208 @11 pcs Room ETB 209, 5 pcs Room Elab 3rd Floor, @9 Room ETB 305, 5 pcs Room ETB 304 @ 1 pc Female IT Faculty 3rd Floor @3 pc Male IT Faculty 3rd Floor -Clear Glass 30cmx55cm, 4 pieces @ 1 pc Room Soil and Water Lab. Room @ 1 pc Room Technical lab @ 1 pc Room ETB 206 @ 1 pc Room ETB 301 -Clear Glass 40cmx65cm,2 pieces @ 1 pc Room ETB 202 @ 1 pc Room ETB 102 -Clear Glass 50cmx70cm,2 pieces @ 2 pc Room Soil and Water Lab. Room -Clear Glass 30cmx30cm,16 pieces @ 9 pc Room Soil and Water Lab. Room @ 5 pc Room Technical lab @ 2 pc IEIT Accreditation Room -Clear Glass 30cmx45cm, 8 pieces @ 8 pcs Right Wing Cr Ground Floor

Prepared by :

JORDAN S. ESTELONG
 KSU PROJECT IN-CHARGE

Checked By:

Engr. CHRISTIAN LOUIE B. ADORA
 Chairman for Planning

Recommending Approval:

Engr. RHONJHON R. GARMING
 Director for Planning and Strategy

Approved By:

EDUARDO T. BAGTANG, CPA, DBM
 President

Republic of the Philippines
KALINGA STATE UNIVERSITY
 Bulanao, Tabuk City, Kalinga

SCOPE OF WORK

Name of Project : ENGINEERING BUILDING REPAIR			
Location : KSU BULANAo CAMPUS, BULANAo, TABUK CITY			
ITEM	ITEMS OF WORK TO BE DONE	UNIT	SCOPE OF WORKS
1100	ELECTRICAL WORKS	sets	10.00
			-Junction Box @ 1pc Room ETB 203 -Two gang Switch (wide Series), 7 pieces @ 3 pcs Third Floor Stair Landing @ 4 pcs Second Floor Stair Landing -Two gang outlet set, 2 pieces @ 1 pc 4th Floor Left Wing @ 1 pc 3rd Floor Lab. 02 -LED Lamps(12 watts), 54 pieces @ 13 pcs 2nd Floor Hallway @ 1 pc Room ETB 203 @ 22 pcs 3rd Floor Hallway and Rooms @ 16 pcs 4th Floor Hallway and Rooms @ 2 pc Infrastructure Room -Ceiling Fun 3d(Standard) @ 1pc 4th Floor Right Wing -Flourescent Light(18 Watts), 6 pieces @ 2 pcs Infrastructure Room @ 2 pcs 4th Floor Right wing @ 2 pcs 4th Floor Left wing @ 2 pcs 4th Floor Center Room -2x18 Watts Flourescent Lamp with Complete housing, 4 pieces @ 2 pcs 4th Floor Right Wing @ 2 pcs 4th Floor Left Wing -Repair Ceiling Fun 3d(Standard) @ 1 pc 4th Floor Right Wing @ 3 pcs 4th Floor Left Wing
1030(d4)	ACOUSTICAL CEILING	sq. m.	29.00
			-Ordinary Plywood 1/4 x 1.2 x 2.4 @ Room ETB 207 -CW nail x 25 -Stick Glue 1/4 Liter
1013(2b)	TINNERY WORKS	ln.m	108.00
			-Prepainted Wall flashing (0.60mx2.4m), 20 pieces @ Grid 1 (I-B) @ Grid 15 (I-D) -Prepainted Gutterx2.4, 1 piece @ Grid 12 (E-D) -Wall Flashing, 13 pieces @ Grid J (2-4) @ Grid J (12-14) @ Grid C (1-4) @ Grid D (13-15) -Fabricated Wall Flashing, 4 pieces @ Grid I (1-2) @ Grid I (14-15) -End Flashing, 4 pieces @ Grid 2 (J-I) @ Grid 14 (J-I) *Blind Rivets *All Purpose Epoxy 1/4 Lit *Vulca Seal 1/4 lit *Concrete Nail 1 1/2
1005	STEEL WINDOWS	sq.m	1.37
			-Chiselling of Window Casement Type(.50x1.37), 2 pieces @ CR Ground Floor Right Wing -Installation of Window Casement Type(.50x1.37), 2 pieces @ CR Ground Floor Right Wing
SPL	Concrete Mouldings	SPL	3.20
			-1.7m mouldings @ 3rd Floor -1.5m mouldings @ 4th Floor

Prepared by :

JORDAN S. ESTELONG
 KSU PROJECT IN-CHARGE

Checked By:

Engr. CHRISTIAN LOUIE B. ADORA
 Chairman for Planning

Recommending Approval:

Engr. RHONJHON R. GARMING
 Director for Planning and Strategy

Approved By:

EDUARDO T. BAGTANG, CPA, DBM
 President

Republic of the Philippines
KALINGA STATE UNIVERSITY
 Bulanao, Tabuk City, Kalinga

SCOPE OF WORK

Name of Project : ENGINEERING BUILDING REPAIR			
Location : KSU BULANAO CAMPUS, BULANAO, TABUK CITY			
ITEM	ITEMS OF WORK TO BE DONE	UNIT	SCOPE OF WORKS
1032(1)b	PAINTING (WOOD)	sq.m.	42.00
			-covers Item @ Male Cr 4th Floor, specified in the plan
			-covers Item @ Male Cr 4th Floor, specified in the plan
			-covers Item Ceiling @Cr 2nd Floor Near ETB 203, specified in the plan
			-covers Item Ceiling @Cr 3rd Floor Near ETB 303, specified in the plan
			-specs are as follows:
			*Permacoat Flat white
			*Rawsiena Acritynt color 1/4 lit
			*Permacoat Choco Brown
			*Masonry putty
			*Sand paper # 200
			*Rollerbrush with pan
			*Paint Brush x 100
			*Paint Brush x 75
			*Paint Brush x 50
			*Roller brush foam
			*Paint Thinner
			*Putty Knife
1032(1)a	PAINTING (MASONRY/CONCRETE)	sq.m.	42.00
			-covers Item @ Wall Female Cr 4th Floor, specified in the plan
			-covers Item @ Wall Female Cr 4th Floor, specified in the plan
			-specs are as follows:
			Latex Flat White
			Oil Based Rawsiena Tinting Color 1/4 lit.
			Sand Paper # 200
			Paint Thinner
			Roller Brush Medium Size faom
			Roller Paint Brush M/S w/ pan
			Paint Brush x 100
			Paint Brush x 75
			Paint Brush x 50
SPL - V	PROJECT BILLBOARD	piece	1.00
			1/4" x 4' x 8' marine plywood
			good lumber
			tarpauline (4' x 8')
			CWN (assorted)

Prepared by :

JORDAN S. ESTELONG
 KSU PROJECT IN-CHARGE

Checked By:

Engr. CHRISTIAN LOUIE B. ADORA
 Chairman for Planning

Recommending Approval:

Engr. RHONJHON R. GARMING
 Director for Planning and Strategy

Approved By:

EDUARDO T. BAGTANG, CPA, DBM
 President