

## Republic of the Philippines

## KALINGA STATE UNIVERSITY

Bulanao, Tabuk City, Kalinga

PROJECT: REPAIR OF HRM BUILDING

LOCATION: KSU BULANAO CAMPUS, TABUK CITY, KALINGA

ITEM No.	ITEMS OF WORK	QTY	UNIT	SCOPE OF WORKS
1013	TINNERY WORKS	23.50	Ln.m	-covers item @ roofing at first floor
				Specs are as follows:
				Tile span roofing(tuscan brown) 1.90m
				Tile span roofing (Tuscan brown) 6.50m
				Valley Gutter(0.6m width)
				vulca seal 1/4 liter
				tekscrew x 55
				all purpose epoxy 1/4 liter
1036(1)a	DOLVCARRONATE SHEET(SOLID)	10.44	sq.m	
	POLYCARBONATE SHEET(SOLID)	19.44	Sq.m	-covers items for grid 2-3(A-B)
				Specs are as follows:
				polycarbonate roofing sheet(2.5mmx1.20mx4.05m)
				Silicon Sealant tube
				Silicon Gun
(000(1) 0		44.00		tekscrew x 55
1032(1)a2	PAINTING(WOOD)	41.30	sq.m	-covers items for ceiling @ 2nd floor and baking laboratory
				-covers items ceiling @ 2nd floor and kitchen for the mouldings
				Specs are as follows:
				Enamel Flat White
				Enamel Gloss White
				Sand Paper # 200
				Paint Thinner
				Roller Brush Medium Size faom
				Roller Paint Brush M/S w/ pan
				Paint Brush x 100
				Paint Brush x 75
				Paint Brush x 50
1007(1)b	ALUMINUM GLASS DOORS	5.04	sq.m	-covers items @ D-1 ( two sets)
				Specs are as follows:
				Butterfly Panel Door with glass(6mm Thick Glass)
				Yale hinges
				kwikset double lock
				kwikset cilindrical
1027	CEMENT PLASTER FINISH	160.00	sq.m	-covers items @ sidings of gutter
				-covers items @ sidings of cabinet
				Specs are as follows:
				sand
4004(0)	FLOOD TODDING/DLANS	4.00		cement
1021(3)	FLOOR TOPPING(PLAIN)	1.20	cu.m	-covers items @ baking laboratory
				Specs are as follows:
				Cement
4040	THE SWODING	0.70		Sand (Fine)
1018	TILEWORKS	0.72	sq.m	-covers items @ baking laboratory
				Specs are as follows:
				tile (0.6x0.6m)
				Tile Grout
4000(14)	A COLUCTION OF WIND	40.00		Tile Cutter Disk
1030(d4)	ACOUSTICAL CEILING	46.08	sq.m	-covers items for ceiling @ 2nd floor and baking laboratory
				Specs are as follows:
				Marine Plywood 1/4" x 1.2 x 2.4
				CW nail x 25
	]			Stickwell glue 1/4 liter

ITEM No.	ITEMS OF WORK	QTY	UNIT	SCOPE OF WORKS
1002.2.5	PLUMBING FIXTURES AND FITTINGS	1.00	lot	-covers items @ CR Male ground and sink at baking laboratory
				Specs are as follows:
				Tile Grout
1020(1)	VINYL FLOOR TILES	16.00	sq.m	-covers items @ reception area at 2nd floor
				Specs are as follows:
				Adhesive
				vinyl floor tile
1002(28)	Water Supply Pipes and Fittings	60.00	ln.m	Specs are as follows:
				G.I Pipe(12.77mmD)
				G.I Coupling elbow(12.77mmD)
				G.I Tee, Banded(12.77mmD)
				G.I Reducer(12.77mmD)
				G.I Reducer(25.44mmD)
				G.I Pipe(25.44mmD)
				G.I union
				Teplon(12 rolls)
				gate valve(25.44mm)
SPL - V	PROJECT BILLBOARD	1.00	piece	Specs are as follows:
				1/4" x 4' x 8' marine plywood
				good lumber
				tarpauline (4' x 8')
				CWN (assorted)

Prepared by:

**JORDAN S. ESTELONG**KSU PROJECT IN-CHARGE

Checked by:

Engr. CHRISTIAN LOUIE B. ADORA

Recommending Approval: Engr. RHONJHON R.GARMING

Chairman for Planning

Approved:

Director for Planning and Strategy

EDUARDO T. BAGTANG, CPA, DBM

SUC President III