

ANNEX "A" - SCOPE OF WORKS

	KALINGA STATE UNIVERSITY OFFICE OF THE PLANNING AND STRATEGY	Doc. Ref. No.:	OPS-CD-H-02
		Effective Date:	JAN. 24, 2019
		Revision No.:	2
		Page no.:	1

PROJECT: Repair for Poultry Floor Framing & Deepwell
 LOCATION: KSU Bulanao Campus, Tabuk City, Kalinga

ITEMS NO.	ITEMS OF WORK	QTY	UNIT	SCOPE OF WORKS
1003(6)	FLOOR FRAMING	376.00	bd. Ft.	- Covers replacement of all non-stiff framing of the structure and placement of vertical framing to the rear side of the building .
				- Covers application of solignum to the whole framing of the structure.
801	REMOVAL OF OBSTRUCTIONS	376.00	bd. Ft.	-Covers removal of non-stiff floor framing of the structure.
1002(5)	WATER SUPPLY PIPES AND FITTINGS	36.00	l. m.	-Covers items of piping system from the deepwell to the poultry structure to be supplied with water.
1201(1)	WATER PUMPING SYSTEM	1.00	lump sum	-Covers items of submersible pump/ pumping system to be installed in the deepwell.
SPL	RENOVATION OF EXISTING DEEPWELL	1.00	lump sum	-Covers the existing deepwell, excavation until water sippage is found.
B.5	PROJECT BILLBOARD	1.00	pc	-Covers project sign board of the building construction.

Page 1 of 1

Prepared by:

KSU INFRA DEPARTMENT

Checked by:

Recommending Approval:

Engr. CHRISTIAN LOUIE B. ADORA
 Chairman for Planning

Engr. RHONJHON R. GARMING
 Director for Planning and Strategy

Approved:

EDUARDO T. BAGTANG, CPA, DBM
 SUC President III

The only controlled copy of this document is the original signed copy maintained in the office of the Planning and Strategy. The reader must ensure that this or any other copy of a controlled document is current and complete prior to use. The duplicate certified copy of this document is with the Records officer. This document is UNCONTROLLED when downloaded and printed.