

Annex "A": scope of works



Republic of the Philippines
KALINGA STATE UNIVERSITY
 Bulanao, Tabuk City, Kalinga

PROJECT: LAND RIPRAP AT RIZAL CAMPUS
 LOCATION: KSU, Rizal Campus, Tabuk, Kalinga

ITEM No.	ITEMS OF WORK	QTY	UNIT	SCOPE OF WORKS
800	CLEARING, GRUBBING AND LAY-OUT	67.50	sq. M.	Lay out of Riprap specified in the plan
802	STRUCTURE EXCAVATION	71.75	cu. m.	-excavation of Riprap foundation and wall footing
1705	FILL AND BACKFILL	58.37	cu. m.	-backfilling and tamping of excavated materials to bleachers
1710(2)a	GRAOUTED RIPRAP "Class A"	74.51	cu. m.	Class A grouted riprap specified in the plan Includes weep hole pipe PVC 75mm dia with filter cloth
900	CONCRETE WORKS	5.66	cu. m.	-all concrete shall be class A - $f_c' \geq 21$ MPa -concreting of slab on fill, bleacher beam and wall footing
404	REINFORCING STEEL BARS	518.54	kgs.	-all reinforcing bars shall be grade 33 $f_y \geq 276$ Mpa -reinforcing bars for slab on fill, bleacher beam and wall footing specs are as follows: *GRADE 33 RSB *no. 16 GI Tie wire
506	MASONRY WORKS (CHB walls)	10.85	sq.m.	-covers zocalo wall specified in the plan specs are as follows: *4" thk. CHB *sand *cement *10mm dia reinforcing steel bars *no. 16 GI tie wire
B-2	PROJECT BILLBOARD	1.00	set	-covers project signboard 8 feet x 4 feet tarpauline framed plywood

Prepared by:
KSU Infrastructure Unit

Engr. CHRISTIAN LOUIE B. ADORA
 Chairman for Planning

Checked by:

Recommending Approval:

Engr. RHONJHON R. GARMING
 Director for Planning and Strategy

Approved:

EDUARDO T. BAGTANG, CPA, DBM
 SUC President III