

Republic of the Philippines KALINGA STATE UNIVERSITY

Bulanao, Tabuk City, Kalinga

Name of Project: RENOVATION OF ACCOUNTING OFFICE KSU BULANAO CAMPUS, TABUK CITY, KALINGA Location:

ITEM No.	ITEMS OF WORK	QTY	UNIT	SCOPE OF WORKS
101(1)	Removal of Structures and Obstruction	1.00	lumpsum	-covers item @
				*Chiseling of Concrete Walls
				*Removal of wall w/frame (plywood)
				*Removal of window(analok)
				*Chiseling of concrete for floor outlet and wall outlet
				*Chiseling of tiles flooring
				*Removal of aluminum frame(partition)
				*Removal of aluminum glass door(partition)
				*Removal or/cutting of steel bars
				*Removal of counter table
				*Chiselling of concrete gutter and drainage wall
1027(1)	CEMENT PLASTER FINISH	7.31	sq.m	-covers item @
				-cement plastering of columns, affected walls and concrete gutter
				specs are as follows:
				sand
				cement
1018(7)	GLAZED TILES	15.48	sq.m.	-covers item @
				-accounting office and cashier area
				specs are as follows:
				600mm x 600mm Glazed Tiles (see existing tiles)35 pieces
				Cement
				Sand
				Tile Grout Fix All and Tile Adhesive
				Tile Cutter Disk
1032(1)a1	PAINTING MASONRY/CONCRETE	23.73	sq.m	-covers item @
				-accounting office and cashier area
				specs are as follows:
				Flat white Latex (1st Coat)
				Final Paint(2nd coat and 3rd coat-verify paint color)
				Masonry putty
				Sand paper
				Paint Brush x 75
1001(9)	STORM DRAINAGE AND DOWNSPOUT	1.00	Lumpsum	-covers item @
			Lampoun	-concrete gutter
				specs are as follows:
				3"dia x 3 PVC PIPE(Series 1000)
				3"dia x 3 PVC ELBOW
				SOLVENT 200 cc
				Fed Seal/Vulcaseal 1 lit
				Silicon Sealant(for roofing)
				Silicon Gun
				-
1100	ELECTRICAL WORKS	1.00	Lumpsum	-covers item @
		1.00	Lumpoum	-accounting office
				specs are as follows:
				Floor pop-up convenience outlet, with shutter, 16A
				Duplex convenience outlet, 46A, 230V
				Surface mounted utility box
				3 gang switch, wide series
				PVC moulding conduit, 1/2"
				3.5mm sq THHN wire, ISO certified
				Electrical Tape

Page 1 of 1

Prepared by:

JORDAN'S ESTELONG
KSU PROJECT IN-CHARGE

Checked by:

Engr. CHRISTIAN LOUTE B. ADORA Chairman for Planning

Approved:

Recommending Approval:

Engr. RHONJHON

Director for Planning nd Sty

EQUARDO T. BASTANG, CPA, DBM SU¢ President II