



**Kalinga State University
PROCUREMENT MANAGEMENT OFFICE
Scope of Works**

Doc. Ref. No.:	KSU-PMO-06_Annex
Effectivity Date:	January 3, 2019
Revision No.:	00
Page No.:	Page 1

Annex "A": Scope of Works

Control No. :

SCOPE AND COVERAGE OF THE PROJECT WITH SPECIFICATION

ITEM No.	ITEMS OF WORK	QTY	UNIT	SCOPE OF WORKS
1021	PLAIN CEMENT FLOOR FINISH	354.16	sq.m.	-topping at south and north bleachers (25mm thick) Specs are as follows: Portland cement Sand
1032(1)a1	PAINTING MASONRY/ CONCRETE	163.37	sq.m.	-covers item at south and north bleachers -all riser will be painted (verify color first before painting) -full putty of all risers until smoothen Specs are as follows: Flat white Latex (1 st coat Final Paint (2 nd coat and 3 rd coat – verify paint color) Masonry Putty Sand paper Rollerbrush with pan Putty Knife
b-2	PROJECT BILLBOARD	1.00	set	-project billboard at Gymnasium Specs are as follows: 1/4"x4'x8' marine plywood Good lumber Tarpaulin (4'x8') CWN (assorted)

Prepared by:

Checked and verified:

KSU INFRASTRUCTURE UNIT

ENGR. CHRISTIAN LOUIE B. ADORA

Chairman for Planning

Recommending Approval:

Approved by:

RHONJHON R. GARMING, MECE
Director for Planning and Strategy

EDUARDO T. BAGTANG, CPA, DBM
KSU President

The only controlled copy of this document is the original signed copy maintained in the Procurement Management Office. The reader must ensure that this or any other copy of a controlled document is current and complete prior to use. The duplicate certified copy of this document is with the Records Office. The user should secure the latest revision of this document from the Procurement Management Office. This document is UNCONTROLLED when scanned, photocopied or downloaded.