



Republic of the Philippines  
**KALINGA STATE UNIVERSITY**  
Bulanao, Tabuk City, Kalinga

PROJECT: **BANTAYOG NG WIKA SCULTURE, BASE & PEDESTAL**

LOCATION: **KSU Bulanao Campus, Tabuk City, Kalinga**

ITEM No.	ITEMS OF WORK	QTY	UNIT	SCOPE OF WORKS
803(1)a	STRUCTURE EXCAVATION(Common soil)	3.89	cu.m	-covers item specified in the plan includes excavation of Pedestal Column Footing.
804(1)a	EMBANKMENT (Selected Fill Materials above Grade)	3.35	cu.m	-covers item specified in the plan includes backfilling of excavated materials
900(1)c1	STRUCTURAL CONCRETE *Footing	0.97	cu.m	-all concrete shall be class A = $f_c' \geq 21$ Mpa -covers item specified in the plan *portland cement *sand *gravel 1"
900(1)c2	STRUCTURAL CONCRETE (COLUMN) * Pestal Column	0.30	cu.m	-all concrete shall be class A = $f_c' \geq 21$ Mpa -covers item specified in the plan '-specs are as follows: *portland cement *sand *gravel 1"
900(1)c3	STRUCTURAL CONCRETE (COLUMN) * Pedestal @ Top	3.23	cu.m	-all concrete shall be class A = $f_c' \geq 21$ Mpa -covers item specified in the plan '-specs are as follows: *portland cement *sand *gravel 1"
903(2)	FORMS & FALSEWORKS	10.47	sq.m	- it is suggested that the staging and scaffoldings should be lumbers '-specs are as follows: *1/2" thk. plywood *good lumbers *common wire nails (assorted)
902	REINFORCING STEEL BARS	275.178	kgs	-all reinforcing bars shall be grade 40 $f_y \geq 276$ Mpa '-specs are as follows: *Grade 40 RSB *no. 16 GI Tie wire

Page 1 of 2

Prepared by:

KSU INFRA. DEPARTMENT

Checked by:

Engr. CHRISTIAN LOUIE B. ADORA  
Chairman for Planning

Recommending Approval:

Engr. RHONJHON R. GARMING  
Director for Planning & Strategy

Approved:

EDUARDO T. BASTANG, CPA, DBM  
President



Republic of the Philippines  
**KALINGA STATE UNIVERSITY**  
Bulanao, Tabuk City, Kalinga

PROJECT: **BANTAYOG NG WIKA SCULPTURE, BASE & PEDESTAL**

LOCATION: **KSU Bulanao Campus, Tabuk City, Kalinga**

ITEM No.	ITEMS OF WORK	QTY	UNIT	SCOPE OF WORKS
1018(1)	TILING WORKS(Glazed Tiles & Trims)	10.75	sq. m.	-covers item specified in the plan -specs are as follows: * 600mm x 600mm Non-skid Granite Floor Tiles * Cement * Sand * Tile Grout Fix All * Tile Cutter Disk <b>NOTE: VERIFY THE COLORS</b>
1100	LIGHTING FIXTURES	1	Outlet	-covers item specified in the plan -specs are as follows: Ground rod, 3m * 15mm inside diameter PVC pipe * NEMA 3r BOX * Locknut and adapter 15mm dia * Groumet sealant * 3.5mm sq THHN wire * 2.0mm sq THHN wire * 18w LED globe bulb * Receptacle * Black screw

Page 2 of 2

Prepared by:

KSU INFRA. DEPARTMENT

Checked by:

Engr. **CHRISTIAN LOUIE B. ADORA**  
Chairman for Planning

Recommending Approval:

Engr. **RHON JHON R. GARMING**  
Director for Planning & Strategy

Approved:

**EDUARDO T. BAGTANG, CPA, DBM**  
President