



Republic of the Philippines
KALINGA STATE UNIVERSITY
 Bulanao, Tabuk City, Kalinga

PROJECT: **CONSTRUCTION OF MOTORPOOL**
 LOCATION: **KSU Bulanao Campus, Tabuk City, Kalinga**

ITEM No.	ITEMS OF WORK	QTY	UNIT	SCOPE OF WORKS
800(1)	Clearing Grubbing & Lay-out	576.00	sq. M.	-covers item @ grid A'-E and 1-4 at ground floor
803(1)	Structure Excavation	82.19	cu. m.	-covers item @ grid A'-E and 1-4 at ground floor
804	Embankment (Selected fill materials above grade)	82.61	cu. m.	-covers item @ grid A'-E and 1-4 at ground floor
900	Concrete works	13.87	cu. m.	-all concrete shall be class A = $f_c' \geq 21$ Mpa
	a. Column Footings			-covers item @ grid A'-E and 1-4 at ground floor (Height = 1.3m)
404	Reinforcing steel bars	2626.45	kgs.	-all reinforcing bars shall be grade 40 $f_y \geq 276$ Mpa

Footings & Column Footings Only
Backfilling of Excavated Materials

Prepared by:
KSU INFRASTRUCTURE

Checked by:

Engr. CHRISTIAN LOUIE B. ADORA
 Chairman for planning

Arch. DAVE D. OGNAT
 Chairman for infrastructure

Recommending Approval:

Engr. RHONJHON R. GARMING
 Director for Planning

Approved:

EDUARDO T. BAGTANG, CPA, DBM
 SUC President III