

## Republic of the Philippines

## KALINGA STATE UNIVERSITY

Bulanao, Tabuk City, Kalinga

PROJECT: CONSTRUCTION/REHABILITATION OF CESSPOOL TANKS

LOCATION: KSU, Bulanao Campus, Tabuk City, Kalinga

| ITEM No.   | ITEMS OF WORK  | QTY   | UNIT            | SCOPE OF WORKS  |
|------------|--|-------|-----------------|---|
| 100 (2)    | CLEARING AND GRUBBING                                    | 1.00  | Lump Sum        | Covers removal of roots of trees along infront of Law Building, |
|            |  |       |                 | infront of IAF Building(right side), and @ the back of          |
|            |  |       |                 | CCJE & DMAT Building near the right side of HRM Building        |
|            |  |       |                 | (Specified in the plan)   |
|            |  | 4.20  | sq.m.           | CLEARING AND GRUBBING   |
|            |  |       |                 | *Materials/Specifications are as follows:                       |
|            |  |       |                 | NONE  |
| 803 (1) a  | STRUCTURE EXCAVATION                                     | 92.82 | cu. m.          | covers minimum excavation of 500mm depth along SEWER LINES @:   |
|            |  |       |                 | * Back & Left side of CTE Buiding                               |
|            |  |       |                 | * Infront of Reaserch, Agriculture & Forestry                   |
|            |  |       |                 | Laboratory Building   |
|            |  |       |                 | * Back of Engineering Building along road side                  |
|            |  |       |                 | * Left & right side of Engineering Building                     |
|            |  |       |                 | * Back of Admin. Building(Left & Right side)                    |
|            |  |       |                 | * Back of High School Building                                  |
|            |  |       |                 | * Back of Library Building (Left & Right side)                  |
|            |  |       |                 | * back of CCJE & DMAT Building near the right side              |
|            |  |       |                 | of HRM Buildng  |
|            |  |       |                 | * Infront of LAW Building (left side)                           |
|            |  |       |                 | *hydraulic testing of water level flow before termination       |
|            |  |       |                 | *Materials/Specifications are as follows:                       |
| 004        | EAST AND AND ASSESSED TO                                 | 20.00 |                 | NONE  |
| 804        | EMBANKMENT   | 90.86 | cu. m.          | cover the item# 803 (1)a  |
|            |  |       |                 | (Specified in the plan)   |
|            |  | -     |                 | *Materials/Specifications are as follows:  NONE                 |
| 101 (1)    | REMOVAL OF STRUCTURE<br>AND OBSTRUCTIONS<br>(Chiselling) | 1.02  | cu. m.          | covers along the pathway of Library & CTE Building              |
|            |  |       |                 | covers along CANALS:  |
|            |  |       |                 | * Back & Left side of CTE Buiding                               |
|            |  |       |                 | * Infront of Reaserch, Agriculture & Forestry                   |
|            |  |       |                 | Laboratory Building   |
|            |  |       |                 | * Back of Engineering Building along road side                  |
|            |  |       |                 | * Left & right side of Engineering Building                     |
|            |  |       |                 | * Catch Basin @ the Back of Admin. Building(Left &              |
|            |  |       |                 | Right side)   |
|            |  |       |                 | * Back of High School Building                                  |
|            |  |       |                 | (Specified in the plan)   |
|            |  |       |                 | *Materials/Specifications are as follows:                       |
|            |  |       |                 | NONE  |
| 1001 (8)   | Sewer Line Works   | 1.00  | <b>Lump Sum</b> | cover the item# 803 (1)a  |
|            |  |       |                 | (Specified in the plan)   |
|            |  |       |                 | *Materials/Specifications are as follows:                       |
|            |  |       |                 | 4" dia. PVC pipes (orange) x 3m S-1000                          |
|            |  |       |                 | PVC Elbow 90 deg. X 100mm dia                                   |
|            |  |       |                 | Solvent Cement 1/4 lit.   |
| 900 (1) a1 | Structural Concrete                                      | 1.02  | cu. m.          | cover the item# 101 (1)   |
|            |  |       |                 | (Specified in the plan)   |
|            |  |       |                 | *Materials/Specifications are as follows:                       |
|            |  |       |                 | . portland cement   |
|            |  | •     |                 |   |

| ITEM No. | ITEMS OF WORK | QTY   | UNIT            | SCOPE OF WORKS                              |
|----------|---------------|-------|-----------------|---|
|          |               |       |                 | . sand                                      |
|          |               |       |                 | . gravel 1"                                 |
| SPL-1    | CESSPOOL TANK | 1.00  | <b>Lump Sum</b> | Covers @ the back of:                       |
|          |               |       |                 | * Right side of Engineering Building        |
|          |               |       |                 | * Back of Admin. Building                   |
|          |               |       |                 | (Specified in the plan)                     |
|          |               | 6.43  | cu.m.           | Excavation                                  |
|          |               | 1.06  | cu.m.           | Pouring of Concrete                         |
|          |               | 5.22  | sq.m.           | Formworks Installation                      |
|          |               | 5.22  | sq.m.           | Formworks fabrication                       |
|          |               | 96.25 | kg              | Fab & Instn of Rebars                       |
|          |               | 18.90 | sq.m.           | Laying of CHB                               |
|          |               | 18.90 | sq.m.           | Plastering                                  |
|          |               | 6.00  | l.m.            | Plumbing                                    |
|          |               |       |                 | *Materials/Specifications are as follows:   |
|          |               |       |                 | A. Excavation                               |
|          |               |       |                 | None  |
|          |               |       |                 | B. Concreting Works                         |
|          |               |       |                 | Portland Cement                             |
|          |               |       |                 | 2. Sand (S -1)                              |
|          |               |       |                 | 3. Gravel (1")                              |
|          |               |       |                 | 4. RSB 10 mmØ x 6.0 grade 40                |
|          |               |       |                 | 5. marine plywood 1/2" thk.                 |
|          |               |       |                 | 6.form lumbers                              |
|          |               |       |                 | 7.lumber scaffolds                          |
|          |               |       |                 | 8.common wire nails (assorted)              |
|          |               |       |                 | 9. GI Tiewire # 16                          |
|          |               |       |                 | C. Masonry Rough Works                      |
|          |               |       |                 | 1. Portland Cement                          |
|          |               |       |                 | 2. Sand                                     |
|          |               |       |                 | 3. RSB 10 mmØ x 6.0 grade 40                |
|          |               |       |                 | 4. CHB 4" THK                               |
|          |               |       |                 | 5. GI Tiewire #16                           |
|          |               |       |                 | D. Masonry Finishing Works                  |
|          |               |       |                 | 1. Portland Cement                          |
|          |               |       |                 | 2. Sand                                     |
|          |               |       |                 | E. Plumbing Rough Works                     |
|          |               |       |                 | 1. Moldex PVC Pipe S-1000 x 100mm dia. X 3m |
|          |               |       |                 | 2. Sanitary Tee 87.50 deg. X 100mm dia.     |
|          |               |       |                 | 4. Clean Out 100mm dia.                     |
|          |               |       |                 | 5. Solvent Cement 1/4 lit                   |
|          |               |       |                 | 6. charcoal                                 |

Prepared by:

KSU INFRA DEPARTMENT

Checked by:

Recommending Approval:

Engr. CHRISTIAN LOVIEB. ADORA

Approve

Chairman for Planning

Engr. RHONJESN R GARMING Director for Planning and Strategy

JARDO T. BAGTANG CPA, DBM

SUC President III