



Republic of the Philippines  
**STATE UNIVERSITY**  
Tabuk City, Kalinga

PROJECT: Office Rehabilitation near President's cottage  
LOCATION: KSU Bulanao Campus, Tabuk City, Kalinga

ITEM No.	ITEMS OF WORK	QTY	UNIT	SCOPE OF WORKS
801	Chiselling/Removal of Structures and Obstruction	1.08	cu. m.	Chiselling of Flooring for tiles
1010	Wooden doors and door jamb	4.83	sq. m.	Replacement of front door and CR door
1018	TILE WORKS	25.22	sq. m.	600mm x 600mm Granite tiles for Office 200mm x 200mm Granite tiles for CR
1003(1)c2	Ceiling-Carpentry and Joinery Works	36.50	sq. m.	Ceiling works with 50 x 50 lumber joists spaced at 600mm on center
1100	ELECTRICAL WORKS	4.00	outlets	
			24.00	m 3.5mm2 THHN Stranded Wire (ISO Certified)
			36.00	pcs 2.0mm2 THHN Stranded Wire (ISO Certified)
			4.00	rolls Electrical Tape B/S
			2.00	units Standard Orbit Fan (Metal Blade)
			2.00	units Fluorescent Fixture, 2 x 40W Surface Type w/ Aluminum Protector
			1.00	sets T5 18WATTS
1002.2.5	PLUMBING FIXTURES AND FITTINGS	5.00	sets	Replacement and installation of the following
			2	1. Boysen QDE flat white
			4	Gloss QDE Gloss white
			1	2. Roller Brush w/ pan
			1	3. Paint Brushx25
			1	4. Roller Brush foam
			1	5. Paint Thinner
			10	6. Sand Paper #240
1032(a1)	PAINTING (MASONRY/CONCRETE)	56.27	sq. m.	Painting of Office Interior and Exterior of the building
1032(a2)	PAINTING (WOOD)	36.50	sq. m.	Painting of the Installed Ceiling

Page 1 of 1

Prepared by:

KSU INFRA DEPARTMENT

Checked by:

  
Engr. RHONJHON B. GARMING  
Director for Planning and Strategy

Recommending Approval:

  
AMADO P. IMPER, Ph.D.  
VP for Administration and Finance

Approved:

  
EDUARDO T. BAGTANG, CPA, DBM  
SUC President III