



Standard Form Number : **SF-INFR-34**

SUPPLEMENTAL / BID BULLETIN (SBB)

ADDENDUM NO. 01

This SBB Addendum No. **01** dated July 14, 2017 for the Project, “**Construction of Performing Arts Theater in Bulanao Campus (Package Contract)**” is issued to clarify, modify or amend items in the Bidding Documents. Accordingly, this shall form an integral part of said Documents.

PARTICULARS	CLARIFICATION / AMENDMENT
<p>On Title of Lot 2 Project which is the Completion of Performing Arts Theater – Bulanao Campus, the following indicators shall be revised:</p> <ol style="list-style-type: none"> 1. Paragraph 1 on Section I. Invitation to Bid 2. Item Clauses 1.1, 2, 12.1(b)(ii.2), and 12.1(b)(iii.3) on Section III. Bid Data Sheet 3. Item Clause 1(c) and Scope of Works of the Terms of Reference on Section VI. Specifications 4. Lot 2 Project on Section VIII. Bill of Quantities 5. GCC 1.31 on Section V. Special Conditions of Contract 	<p>The revised title of the Lot 2 Project shall be:</p> <p style="text-align: center;">Completion (for Phase V Construction) of Performing Arts Theater - Bulanao Campus</p> <p>*The title “completion” is supposed to be Phase V Construction since the Performing Arts Theater is pegged at around 26 million pesos.</p>
<p>On Contract Duration or Project Completion period, which is Four Hundred Sixty-nine (469) calendar days, the following indicators shall be revised:</p> <ol style="list-style-type: none"> 1. Paragraph 2 on Section I. Invitation to Bid 2. GCC 1.17 on Section V. Special Conditions of Contract 3. Item Clause 3.5 of the Terms of Reference on Section VI. Specifications 	<p>The new Contract Duration/Project Completion shall be Four Hundred Fourteen (414).</p>
<p>Section VI. Specifications <i>Scope of Works</i> Lot 1: Construction of Performing Arts Theater - Phase IV Lot 2: Completion (for Phase V Construction) of Performing Arts Theater - Bulanao Campus</p>	<p>The revised Scope of Works for each project lot is attached in the next page.</p>
<p>Section VIII. Bill of Quantities <i>BOQ of the following Lot Contracts:</i> Lot 1: Construction of Performing Arts Theater - Phase IV Lot 2: Completion (for Phase V Construction) of Performing Arts Theater - Bulanao Campus</p>	<p>The revised Bill of Quantities for each project lot under Section VIII are attached (next page after Scope of Works).</p>

Notes: This SBB is taken from the Minutes of the Pre-bid Conference held on July 12, 2017.

For guidance and information of all concerned.


 AMADO P. IMPER, PhD
 BAC Chairman

Date Issued: July 14, 2017

Copy furnished: Prospective Bidders



Republic of the Philippines
KALINGA STATE UNIVERSITY
BIDS AND AWARDS COMMITTEE
 National Highway, Purok 6, Bulanao, Tabuk City, Kalinga
 Website: <http://ksu.edu.ph> Email: ksumail@ksu.edu.ph Contact No.: 0917-822-6145

REVISED SCOPE OF WORKS FOR THE CONSTRUCTION OF PERFORMING ARTS THEATER - PHASE IV:



Republic of the Philippines
KALINGA STATE UNIVERSITY
 Bulanao, Tabuk City, Kalinga

PROJECT: **CONSTRUCTION OF PERFORMING ARTS THEATER - PHASE IV**
 LOCATION: **KSU Bulanao Campus, Tabuk City, Kalinga**

ITEM No.	ITEMS OF WORK	QTY	UNIT	SCOPE OF WORKS
800	CLEARING, GRUBBING AND LAY-OUT	661.50	sq.m.	-covers items @ grid A to G & 2 to 9 specified in the plan
803(1)a	STRUCTURE EXCAVATION (Common Soil)	173.60	cu. m.	-covers 26 sets F1, 10 sets F2 and Storm drainage line
804(1)	EMBANKMENT	100.22	cu. m.	-Backfilling of Excavated materials
900	STRUCTURAL CONCRETE	344.44	cu. m.	-all concrete shall be class A - fc' ≥ 21 MPa
				-covers RC structural member items specified below which is not yet done specified in the plan (FORMS AND SCAFFOLDINGS INCLUDED)
	COLUMN FOOTING	31.55	cu. m.	-covers items @ grid A to G & 2 to 9 specified in the plan
	GTB	11.47	cu. m.	-covers items @ grid A to G & 2 to 9 specified in the plan
	COLUMNS	84.40	cu. m.	-covers items @ grid A to N & 2 to 9 specified in the plan
	SECOND FLOOR BEAMS	29.63	cu. m.	-covers items @ grid A to N & 2 to 9 specified in the plan
	THIRD FLOOR BEAMS	43.44	cu. m.	-covers items @ grid A to N & 2 to 9 specified in the plan
	ROOF BEAMS	13.47	cu. m.	-covers items @ grid A to N & 2 to 9 specified in the plan
	SLAB	112.27	cu. m.	-covers items @ grid A to N & 2 to 9 specified in the plan
	STAIRS	12.60	cu. m.	-covers items @ grid A to N & 2 to 9 specified in the plan
	STORM DRAINAGE	2.52	cu. m.	-covers items specified in the plan
	CB & CORBEL	3.09	cu. m.	-covers items @ grid A to N & 2 to 9 specified in the plan
902	REINFORCING STEEL BARS	61,765.74	kgs.	-covers reinforcing steel bars of items specified in Structural Concrete
				-all MAIN reinforcing bars shall be grade 60 fy≥414 Mpa
				-all Ties reinforcing bars shall be grade 40 fy≥345 Mpa
1002	PLUMBING WORKS	168.00	In.m	-covers rough-in pipes and fittings of CRs specified in the plan
				-PVC moldex/Sanimold or equivalent
1100	CONDUITS, BOXES AND FITTINGS	2,625.00	In.m	-covers items @ grid A to N & 2 to 9 specified in the plan
			666 pcs	Conduits, 15mm inside diameter, PVC Pipe
			136 pcs	Conduits, 20mm inside diameter, PVC Pipe
			38 pcs	Conduits, 25mm inside diameter, PVC Pipe
			16 pcs	Conduits, 32mm inside diameter, PVC Pipe
			4 pcs	Conduits, 40mm inside diameter, PVC Pipe
			15 pcs	Conduits, 75mm inside diameter, PVC Pipe
			238 pcs	Elbow for 15mm diameter PVC
			49 pcs	Elbow for 20mm diameter PVC
			9.5 pcs	Elbow for 25mm diameter PVC
			8 pcs	Elbow for 32mm diameter PVC
			2 pcs	Elbow for 40mm diameter PVC
			5 pcs	Elbow for 75mm diameter PVC
			576 pcs	Locknut/ Bushing for 15mm diameter PVC with adaptor
			314 pcs	Locknut/ Bushing for 20mm diameter PVC with adaptor
			10 pcs	Locknut/ Bushing for 32mm diameter PVC with adaptor
			10 pcs	Locknut/ Bushing for 40mm diameter PVC with adaptor
			20 pcs	Locknut/ Bushing for 75mm diameter PVC with adaptor
			288 pcs	Utility box 100mm x 50mm deep type
			352 pcs	Utility box 100mm x 100mm deep type with cover
			1 pcs	Ground Rod, 5/8" diameter, 6ft long with clamp
			118 m	Mica Tube, 15mm diameter
				Note: Excludes Conduits for ground floor slab and Ceiling

Page 1 of 2

Prepared by:

KSU INFRASTRUCTURE UNIT

Checked by:

Engr. RHONJHON R. GARMING
 Director for Planning & Strategy

Recommending Approval:

AMADO P. IMPER, Ph. D.
 VP. for Admin & Finance

Approved:

EDUARDO T. BAGTANG, CPA, DBM
 SUC President III

Page 2 of 10



Republic of the Philippines
KALINGA STATE UNIVERSITY
BIDS AND AWARDS COMMITTEE
 National Highway, Purok 6, Bulanao, Tabuk City, Kalinga
 Website: <http://ksu.edu.ph> Email: ksuemail@ksu.edu.ph Contact No.: 0917-822-6145



Republic of the Philippines
KALINGA STATE UNIVERSITY
 Bulanao, Tabuk City, Kalinga

PROJECT: CONSTRUCTION OF PERFORMING ARTS THEATER - PHASE IV
 LOCATION: KSU Bulanao Campus, Tabuk City, Kalinga

ITEM No.	ITEMS OF WORK	QTY	UNIT		SCOPE OF WORKS
1101	WIRES AND WIRING DEVICES	7,861.29	In.m.		-covers items @ grid A to N & 2 to 9 specified in the plan
					Note: Excludes Wires for ground floor slab and Ceiling
				m	284 Wire # 2.0mm ² THHN copper stranded 600V (Green)
				m	2016 Wire #3.5mm ² THHN copper stranded 600V (Red)
				m	2016 Wire #3.5mm ² THHN copper stranded 600V (White)
				m	2016 Wire #3.5mm ² THHN copper stranded 600V (Green)
				m	306 Wire #5.5mm ² THHN copper stranded 600V (Red)
				m	306 Wire #5.5mm ² THHN copper stranded 600V (White)
				m	306 Wire #5.5mm ² THHN copper stranded 600V (Green)
				m	15 Wire #8.0mm ² THHN copper stranded (Red)
				m	15 Wire #8.0mm ² THHN copper stranded (Blue)
				m	15 Wire #8.0mm ² THHN copper stranded (White)
				m	10 Wire #8.0mm ² THHN copper stranded (Green)
				m	68 Wire #14mm ² THHN copper stranded 600V (Red)
				m	68 Wire #14mm ² THHN copper stranded 600V (Blue)
				m	68 Wire #14mm ² THHN copper stranded 600V (White)
				m	68 Wire #14mm ² THHN copper stranded 600V (Green)
				m	15 Wire #30mm ² THHN copper stranded 600V (Red)
				m	15 Wire #30mm ² THHN copper stranded 600V (Blue)
				m	15 Wire #30mm ² THHN copper stranded 600V (White)
				m	15 Wire #22mm ² THHN copper stranded 600V (Green)
				m	40 Wire #38mm ² THHN copper stranded 600V (Red)
				m	40 Wire #38mm ² THHN copper stranded 600V (Blue)
				m	40 Wire #38mm ² THHN copper stranded 600V (White)
				m	25 Wire #50mm ² THW copper stranded 600V (Green)
				m	10 Wire #80mm ² THHN copper stranded 600V (Red)
				m	10 Wire #80mm ² THHN copper stranded 600V (Blue)
				m	10 Wire #80mm ² THHN copper stranded 600V (White)
				m	24.1 Wire #150mm ² THW copper stranded 600V (Red)
				m	24.1 Wire #150mm ² THW copper stranded 600V (Blue)
				m	24.1 Wire #150mm ² THW copper stranded 600V (White)
				roll	20 Rubber Tape
				roll	320 Electrical Tape
				cans	129 PVC Solvent Cement
				pcs	157 Convenience outlet, 16A, Duplex, 3prong, 250V
				pcs	25 Weatherproof Convenience outlet, 16A, Duplex, 3prong, 250V
				pcs	22 Aircon Outlet 20A, 1-gang, 3-prong
				assy	1 Manual Transfer Switch 500A, 3P+G, 42KAIC, Free Standing
				pcs	21 Switch, one gang, 10A, 250V
				pcs	57 Switch, two gang, 10A, 250V
				pcs	11 Switch, Three gang, 20A, 250V
B.5	PROJECT BILLBOARD	1.00	piece		8 ft x 8 ft Tarpauline with lumber frame
B.7	OCCUPATIONAL SAFETY AND HEALTH PROGRAM	1.00	lot		-covers safety equipments to be used during the construction which includes first aider and Part time Practicioner

Page 2 of 2

Prepared by:

KSU INFRASTRUCTURE UNIT

Checked by:

Engr. RHONJHON R. GARMING
 Director for Planning & Strategy

Recommending Approval:

AMADO P. IMPER, Ph. D.
 VP. for Admin & Finance

Approved:

EDUARDO T. BAGTANG, CPA, DBM
 SUC President III

Page 3 of 10



REVISED SCOPE OF WORKS FOR THE COMPLETION (FOR PHASE V CONSTRUCTION) OF PERFORMING ARTS THEATER - BULANAo CAMPUS:



Republic of the Philippines
KALINGA STATE UNIVERSITY
 Bulanao, Tabuk City, Kalinga

PROJECT: COMPLETION (FOR PHASE V CONSTRUCTION) OF PERFORMING ARTS THEATER - BULANAo CAMPUS
 LOCATION: KSU Bulanao Campus, Tabuk City, Kalinga

ITEM No.	ITEMS OF WORK	QTY	UNIT	SCOPE OF WORKS
803(1)a	STRUCTURE EXCAVATION (Common Soil)	110.14	cu. m.	-covers all wall footing, Septic tank and sewage man hole
804(1)	EMBANKMENT	272.74	cu. m.	-selected fill materials @ ground level @ grid A to G
1000(1)	TERMITE CONTROL (Soil Poisoning)	661.50	sq. m.	-Application of Lentrek or any equivalent material prior to ground slab
900	STRUCTURAL CONCRETE	110.06	cu. m.	
				-all concrete shall be class A - fc' ≥ 21 MPa
				-covers RC structural member items specified below which is not yet done specified in the plan (includes Forms and Scaffoldings)
	WALL FOOTING	17.87	cu. m.	-covers items @ grid A to G & 2 to 9 specified in the plan
	SLAB on fill and Septic tank top and bottom slab	74.36	cu. m.	-covers items @ grid A to G & 2 to 9 specified in the plan
	SEWAGE MANHOLE	1.54	cu. m.	-covers items @ grid A to N & 2 to 9 specified in the plan
	GUTTER	16.29	cu. m.	-covers items @ grid A to N & 2 to 9 specified in the plan
902	REINFORCING STEEL BARS	61,765.74	kgs.	-covers reinforcing steel bars of items specified in Structural Concrete
				-all MAIN reinforcing bars shall be grade 60 fy≥414 Mpa
				-all Ties reinforcing bars shall be grade 40 fy≥345 Mpa
1046	MASONRY WORKS (CHB walls)	1,469.34	sq.m.	-covers items @ grid A to G & 2 to 9 specified in the plan
				-ground partitions should be 4" thick
				-Exterior Walls should be 5" thick for ground perimeter
				-Septic tank should be 5" thick
				-Partitions and other CHB walls are 4" thick
				-Horizontally and vertically reinforced w/10mm spaced at 600mm OC
1027	CEMENT PLASTER FINISH	2,413.57	sq.m.	-20mm thick cement plaster paper finish
				-covers unfinished items @ grid A to N & 2 to 9 specified in the plan except third floor - Stockroom and control room

Page 1 of 5

Prepared by:

KSU INFRASTRUCTURE UNIT

Checked by:

Engr. RHONJHON R. GARMING
 Director for Planning & Strategy

Recommending Approval:

AMADO P. IMPER, Ph.D.
 VP. for Admin & Finance

Approved:

EDUARDO T. BAGTANG, CPA, DBM
 SUC President III



Republic of the Philippines
KALINGA STATE UNIVERSITY
BIDS AND AWARDS COMMITTEE
National Highway, Purok 6, Bulanao, Tabuk City, Kalinga
Website: <http://ksu.edu.ph> Email: ksumail@ksu.edu.ph Contact No.: 0917-822-6145



Republic of the Philippines
KALINGA STATE UNIVERSITY
Bulanao, Tabuk City, Kalinga

PROJECT: COMPLETION (FOR PHASE V CONSTRUCTION) OF PERFORMING ARTS THEATER - BULANA O CAMPUS
LOCATION: KSU Bulanao Campus, Tabuk City, Kalinga

ITEM No.	ITEMS OF WORK	QTY	UNIT	SCOPE OF WORKS
1047(2)a	METAL STRUCTURES (Roof Rafter)	17,080.00	kgs.	-covers items @ grid A to N & 2 to 9 specified in the plan 1. Rafter HSS 8.9mm x 101.6mm x 177.8mmx8.0m 2. Collar HSS 8.9mm x 101.6mm x 177.8mmx6.0m 3. Rafter & Plate spacer HSS 8.9mm x 101.6mm x 177.8mmx6.0m 4. Flat bar 12mm x 250 x 500 5. Anchor bolt w/ nut A325x16Ø 6. Welding rod 7. Oxy-acetylene (content only) 8. Diagonal tension bracing 16mmØ x 6.0 9. Heavy duty turn buckle 16 Ø x 600 10. Epoxy primer paint/pair 11. Paint thinner 12. Paint brush x 50mm
1047(2)b	METAL STRUCTURES (Purlins)	8,725.64	kgs.	-covers items @ grid A to N & 2 to 9 specified in the plan 1. "C" Section 2.5mm x 2.5mm x 75 x 150 x 6.0m 2. Sagrod RSB 12mmØ x 6.0m 3. Purlin cleats angle bar 6mmx50mmx50mmx6m 4. Flat washer sagrod stopper 50mmØ x12mmØ 5. Welding rod 6. Epoxy primer paint/pair 7. Paint brush x 50mm 8. Paint thinner
1014(1)b 2	PREPAINTED METAL SHEETS	724.80	sq.m.	-covers items @ grid A to N & 2 to 9 specified in the plan 1. GI roof #0.50mm x 1.20 x 8.0m pre-painted long span 2. GI ridge roll #0.50mm x 1.20 x 2.40 3. GI wall flashing #0.50mm x 1.20 x 2.40 4. Teckscrew x 50mm 5. Blind Rivet x 20mm 6. Colored sealant 7. Rubber silicon 8. Drill Bit 9. Fiber Glass sheet 6mm x 1.20 x 2.40 clear

Page 2 of 5

Prepared by:

KSU INFRASTRUCTURE UNIT

Checked by:


Engr. RHONJHON R. GARMING
Director for Planning & Strategy

Recommending Approval:


AMADO P. IMPER, Ph.D.
VP. for Admin & Finance

Approved:


EDUARDO T. BAGTANG, CPA, DBM
SUC President III



Republic of the Philippines
KALINGA STATE UNIVERSITY
BIDS AND AWARDS COMMITTEE
 National Highway, Purok 6, Bulanao, Tabuk City, Kalinga
 Website: <http://ksu.edu.ph> Email: ksumail@ksu.edu.ph Contact No.: 0917-822-6145



Republic of the Philippines
KALINGA STATE UNIVERSITY
 Bulanao, Tabuk City, Kalinga

PROJECT: **COMPLETION (FOR PHASE V CONSTRUCTION) OF PERFORMING ARTS THEATER - BULANA O CAMPUS**
 LOCATION: **KSU Bulanao Campus, Tabuk City, Kalinga**

ITEM No.	ITEMS OF WORK	QTY	UNIT	SCOPE OF WORKS
1008	ALUMINUM GLASS WINDOWS	32.13	sq. m.	-covers items @ grid A to N & 2 to 9 specified for ground floor perimeter Analog 6mm thick Glass on Aluminum Frame 4 sets W3, 2 sets W4, 5 sets W5, 6 sets W6, 2 sets W7, 2 sets W8 & 1 set W9
SPL	ALUMINUM GLASS WINDOW GRILLS	32.13	sq. m.	Aluminum window grills w/ frame for specified Al glass windows
1010	WOODEN DOORS	11.34	sq.m.	-covers items @ grid A to N & 2 to 9 specified for ground floor perimeter 6 sets D-6 Narra Panel Door with door jamb and accessories
1007	ANALOCK GLASS DOORS	9.00	sets	-covers items @ grid A to N & 2 to 9 specified for ground floor perimeter -covers items @ grid A to N & 2 to 9 specified for ground floor perimeter 1set D1, 4 sets D2, 2 sets D3, 2 sets D4, Analog Frame Butterfly 6mm glass Door
1008(1)	ANALOK GLASS PARTITIONS	58.16	sq. m.	-covers items @ grid A to N & 2 to 9 specified for ground floor Modular Partition Analog Frame S-1000 with 10mm thick Tinted Glass -4.6m x 2.4m x 2 sets -2.6m x 2.4m x 4 sets Partition with Doors -4.6m x 2.6m x 1 set -2.1m x 2.6m x 2 sets
1011	ROLL-UP DOORS	7.00	sets	-covers items @ grid A to N & 2 to 9 specified for ground floor -5.4m x 3m x 1 set @ D4 with glass partition -2.5m x 2.8m x 2 sets @ D2 with glass partition -2.1m x 2.8m x 2 sets @ D2 -1.7m x 2.8m 2 sets @ D3
1002	PLUMBING WORKS	9.00	ln.m	-covers rough-in pipes and fittings of Septic Tank specified in the plan
1002(8)	PLUMBING FIXTURES	36.00	sets	-covers fixtures of CRs specified in the plan 1. Water Closet assembly (water closet w/ tank & Lavatory), including Tissue holder, Soap holder (round) 2. Lavatory Assy. (big) w/ faucet, including fittings & accessories American std or equal . 3. Urinal Hang Type Assy. including fittings & accessories (Wash brook) 4. PVC Tile drain 100 x 100 -PVC moldex/Sanimold or equivalent

Page 3 of 5

Prepared by:

KSU INFRASTRUCTURE UNIT

Checked by:

Engr. RHONJHON R. GARMING
 Director for Planning & Strategy

Recommending Approval:

AMADO P. IMPER, Ph.D.
 VP. for Admin & Finance

Approved:

EDUARDO T. BAGTANG, CPA, DBM
 SUC President III

Page 6 of 10



Republic of the Philippines
KALINGA STATE UNIVERSITY
BIDS AND AWARDS COMMITTEE
National Highway, Purok 6, Bulanao, Tabuk City, Kalinga
Website: <http://ksu.edu.ph> Email: ksumail@ksu.edu.ph Contact No.: 0917-822-6145



Republic of the Philippines
KALINGA STATE UNIVERSITY
Bulanao, Tabuk City, Kalinga

PROJECT: **COMPLETION (FOR PHASE V CONSTRUCTION) OF PERFORMING ARTS THEATER - BULANA O CAMPUS**
LOCATION: **KSU Bulanao Campus, Tabuk City, Kalinga**

ITEM No.	ITEMS OF WORK	QTY	UNIT			SCOPE OF WORKS
1002(6)	COLD WATER LINES	108.00	In.m.			-covers PPR pipes and fittings of CR and Water system specified in the plan
1100	CONDUITS, BOXES AND FITTINGS	1149.00	In.m.			-Covers Items for Slab on fill and Ceiling
				285	pcs	Conduits, 15mm inside diameter, PVC Pipe
				60	pcs	Conduits, 20mm inside diameter, PVC Pipe
				38	pcs	Conduits, 25mm inside diameter, PVC Pipe
1101	WIRES AND WIRING DEVICES	3905.70	In.m.			
				752	m	Wire # 2.0mm ² THHN copper stranded 600V (Green)
				244	m	Wire #3.5mm ² THHN copper stranded 600V (Red)
				244	m	Wire #3.5mm ² THHN copper stranded 600V (White)
				244	m	Wire #3.5mm ² THHN copper stranded 600V (Green)
				793.3	m	Wire #5.5mm ² THHN copper stranded 600V (Red)
				793.3	m	Wire #5.5mm ² THHN copper stranded 600V (White)
				793.3	m	Wire #5.5mm ² THHN copper stranded 600V (Green)
				13.9	m	Wire #150mm ² THW copper stranded 600V (Red)
				13.9	m	Wire #150mm ² THW copper stranded 600V (Blue)
				13.9	m	Wire #150mm ² THW copper stranded 600V (White)
						Electrical Tape
1103	LIGHTING FIXTURES	247.00	sets			
				22.00	pcs	Pinlight 18W LED
				111.00	pcs	Pinlight 18W LED (RECESSED TYPE)
				84.00	pcs	Fluorescent Light 2-18W LED
				20.00	pcs	Square Pinlight LED 600x600
				10.00	unit	Exhaust Fan

Page 4 of 5

Prepared by:

KSU INFRASTRUCTURE UNIT

Checked by:

Engr. RHONJHON R. GARMING
Director for Planning & Strategy

Recommending Approval:

AMADO P. IMPER, Ph.D.
VP. for Admin & Finance

Approved:

EDUARDO T. BAGTANG, CPA, DBM
SUC President III

Page 7 of 10



REVISED BILL OF QUANTITIES (BOQ) FOR THE CONSTRUCTION OF PERFORMING ARTS THEATER - PHASE IV:

ITEM NO.	DESCRIPTION	UNIT	Qty.	Unit Price (in Pesos)	Total Cost (in Pesos)
800	CLEARING, GRUBBING AND LAY-OUT	sq.m.	661.50		
803(1)a	STRUCTURE EXCAVATION (Common Soil)	cu. m.	173.60		
804(1)	EMBANKMENT	cu. m.	100.22		
900	STRUCTURAL CONCRETE	cu. m.	344.44		
902	REINFORCING STEEL BARS	kgs.	61,765.74		
1002	PLUMBING WORKS	ln.m	168.00		
1100	CONDUITS, BOXES AND FITTINGS	ln.m.	2,625.00		
1101	WIRES AND WIRING DEVICES	ln.m.	7,861.29		
B.5	PROJECT BILLBOARD	piece	1.00		
B.7	OCCUPATIONAL SAFETY AND HEALTH PROGRAM	Lot	1.00		
TOTAL BID AMOUNT (in figures): Php					
TOTAL BID AMOUNT (in words): Pesos					



**REVISED BILL OF QUANTITIES (BOQ) FOR THE COMPLETION (FOR PHASE V CONSTRUCTION)
OF PERFORMING ARTS THEATER - BULANA O CAMPUS:**

ITEM NO.	DESCRIPTION	UNIT	Qty.	Unit Price (in Pesos)	Total Cost (in Pesos)
803(1)a	STRUCTURE EXCAVATION (Common Soil)	cu. m.	110.14		
804(1)	EMBANKMENT (Selected Fill Materials above Grade)	cu. m.	272.74		
1000(1)	TERMITE CONTROL (Soil Poisoning)	sq. m.	661.50		
900	STRUCTURAL CONCRETE	cu. m.	110.06		
902	REINFORCING STEEL BARS	kgs.	61,765.74		
1046	MASONRY WORKS (CHB walls)	sq.m.	1,469.34		
1027	CEMENT PLASTER FINISH	sq.m.	2,413.57		
1047(2)a	METAL STRUCTURES (Roof Rafter)	kgs.	17,080.00		
1047(2)b	METAL STRUCTURES (Purlins)	kgs.	8,725.64		
1014(1)b2	PREPAINTED METAL SHEETS	sq.m.	724.80		
1008	ALUMINUM GLASS WINDOWS	sq. m.	32.13		
SPL	ALUMINUM GLASS WINDOW GRILLS	sq. m.	32.13		
1010	WOODEN DOORS	sq.m.	11.34		
1007	ANALOCK GLASS DOORS	sets	9.00		
1008(1)	ANALOK GLASS PARTITIONS	sq. m.	58.16		
1011	ROLL-UP DOORS	sets	7.00		
1002	PLUMBING WORKS	ln.m	9.00		
1002(8)	PLUMBING FIXTURES	sets	36.00		
1002(6)	COLD WATER LINES	ln.m.	108.00		
1100	CONDUITS, BOXES AND FITTINGS	ln.m.	1,149.00		
1101	WIRES AND WIRING DEVICES	ln.m.	3,905.70		
1102	POWER LOAD CENTER, SWITCH GEAR AND PANEL BOARD	sets	22.00		
1103	LIGHTING FIXTURES	sets	247.00		
1018	CERAMIC/GRANITE TILES	sq.m.	188.87		
B.5	PROJECT BILLBOARD	piece	1.00		
B.7	OCCUPATIONAL SAFETY AND HEALTH PROGRAM	Lot	1.00		
TOTAL BID AMOUNT (in figures): Php					
TOTAL BID AMOUNT (in words): Pesos					