Name of the Procuring Entity Project Reference Number Name of the Project Location of the Project **End-User Unit** Implementing Unit

Standard Form Number

KALINGA STATE UNIVERSITY

IB_CIVILWORKS_2018-12-67
COMPLETION OF GRADUATE STUDIES AND LAW BUILDING

KSU MAIN CAMPUS, NAT'L HIGHWAY, PUROK 6, BULANAO CENTRO, TABUK CITY, KALINGA HIGHER EDUCATION SERVICES C/O BULANAO CAMPUS ADMINISTRATOR

INFRASTRUCTURE OFFICE



SUPPLEMENTAL / BID BULLETIN (SBB) **ADDENDUM NO. 01**

This SBB Addendum No. 01 dated December 20, 2018 for the Project: Completion of Graduate Studies and Law Building is issued to clarify, modify or amend items in the Bidding Documents. Accordingly, this shall form an integral part of said Documents.

PART	ICULARS
------	----------------

CLARIFICATION / AMENDMENT

On Item No. X-Scope of Works on the Terms of Reference under Section VI-Specifications, page 72-75 of the bid document, the following in highlighted yellow color are the selective revisions/modifications as result of Pre-bid Conference conducted on December 17, 2018 @ 1 pm (for clarity, other items of the scope of works are unchanged):

ITEM No.	ITEMS OF WORK	QTY	UNIT	SCOPE OF WORKS
1027(1)	PLAIN CEMENT PLASTER FINISH	63.79 3.60 18.00 13.80 14.01 3.10 11.29	sq.m	This covers the following areas in reference from the plans: column @ grid A'(3) canopy beam @ grid A'(2-3) canopy beam @ grid F'(2-2') PUMP ROOM: all inside surface all outside surface elevator shaft The following materials are: sand cement
1032(1)a2	Painting Wood	936.61 858.54 78.07	sq.m	This covers the following areas in reference from the plans: CEILING(Gypsum board) CEILING(Fiber Cement Board) The following materials are: Enamel Flat White Enamel Gloss White Sand Paper # 200 Plasolux Glazing Putty Paint Thinner Roller Brush Medium Size foam Roller Paint Brush M/S w/ pan Paint Brush x 100 Paint Brush x 75 Paint Brush x 50 Enamel Choco Brown Scaffolding lumber 2"x2"x3.6m
1003(1)e1	CEILING (Gypsum board)	858.54 705.09 153.45	sq.m	This covers the following areas in reference from the plans: At ground floor to third floor: stair landing, hallway, faculty room, Accreditation room, Moot court and classroom At fourth floor: stair area, meeting room & classroom The following materials are: Gypsum board 9mm x 1.20 x2.40m Metal Furring 20 x 50 x.40mm thk x 5m Metal Furring Clip Wall angle 2" x 5m Concrete nail 1" Gypsum board screw wood cornice X 75mm X 2.40 Blind Rivets x 55 Gypsum Putty Stick well Glue

For guidance and information of all concerned.

Date Issued: December 20, 2018 Copy furnished: Prospective Bidders