



Republic of the Philippines
KALINGA STATE UNIVERSITY
BIDS AND AWARDS COMMITTEE
 National Highway, Purok 6, Bulanao, Tabuk City 3800, Kalinga

Website: <https://ksu.edu.ph> Email: procurementservice_bac@ksu.edu.ph Tel.No.: (074) 627-5321

Standard Form Number : SF-INFR-34

SUPPLEMENTAL / BID BULLETIN (SBB) ADDENDUM NO. 01

This SBB Addendum No. 01 dated October 29, 2019 for the Project: **Completion of Performing Arts Theater** is issued to clarify, modify or amend items in the Bidding Documents. Accordingly, this shall form an integral part of said Documents.

PARTICULARS	CLARIFICATION / AMENDMENT
On Item No. X-Scope of Works on the Terms of Reference under Section VI-Specifications, pages 71-80 of the bid document, the following is the Revised Scope of Works as result of Pre-bid Conference conducted on October 24, 2019 @ 10am:	

ITEM No.	ITEMS OF WORK	QTY	UNIT	SCOPE OF WORKS
1046(2)a1	100 mm CHB Non-Load Bearing Wall (including Reinforcing Steel)	640.50	sq.m.	This covers the following areas in reference from the plans:
		128.23		Ground Floor
				Security office
				Grid J(4') stair landing
				Grid 3&8(G-H)
				Backstage
				Center aisle
		205.61		Second floor
				Grid 6(H-J), CR & Record room, Grid H(5-6), Grid 4&7(I-J), Grid 2&7(A-C), Grid N(5-6), Grid I(4-5), Grid 4&7(C-F), Grid 4&7(J-K)
		28.80		Second floor multi-purpose deck
				Grid C(2-4)&(7-9), Grid 2&9(C-F)
		282.68		Third floor
				Grid I(4-5)&(6-7), Grid J(4-5)&(6-7), Grid I(5&6), Grid 4&7(F-G), Grid 4&7(G-H), Grid 4&7(H-I), Grid 4&7(I-J), Grid 4&7(E-F), Grid 4&7(C-E), Grid 4&7(B-C), Grid 4&7(A-B), Grid 4&7(J-K), Grid 4&7(K-L), Grid 4&7(L-M), Grid 5&6(M-N), Grid 2&6(F-G), Grid F&G(2-3)&(8-9), Grid 4&7(A-M')
		28.20		Parapet wall
				Grid A-M (4-7)
				The following materials are:
				4" thick CHB
				sand
				cement
				10mm dia. RSB Grade 40
				no. 16 GI tie wire
404	REINFORCING STEEL BARS	272.70	kgs	This covers the reinforcements for the stairs located @ grid I-J (4-5)
				The following materials are:
				GRADE 40 RSB
				no. 16 GI Tie wire
900	CONCRETE WORKS	3.59	cu.m	This covers the concreting of stairs located @ grid I-J (4-5)
				The following materials are:
				Portland Cement
				Sand
				Gravel 1"



Republic of the Philippines
KALINGA STATE UNIVERSITY
BIDS AND AWARDS COMMITTEE

National Highway, Purok 6, Bulanao, Tabuk City 3800, Kalinga

Website: <https://ksu.edu.ph> Email: procurementservice_bac@ksu.edu.ph Tel.No.: (074) 627-5321

ITEM No.	ITEMS OF WORK	QTY	UNIT	SCOPE OF WORKS
903(2)	FORMS AND FALSE WORKS	20.96	sq.m	This covers the formworks of stairs located @ grid I-J (4-5) The following materials are: 1/2" thick Ordinary Plywood 1.2m x 2.4m form lumbers common wire nails (assorted)
1027(1)	PLAIN CEMENT PLASTER FINISH	3,438.59 1,281.00 225.70 183.15	sq.m.	This covers the following areas in reference from the plans: CHB WALLS Grid 2 & 9 (that were not covered in Phase V) Grid A Ground Floor (Grid GM(4-7)) CR Grid I'(4') CR GRID I'(7') Grid I'(7') stair landing Grid 4&7(K-M) Grid M(4-5 & 6-7) Grid M(5-6) Columns beams stairs concrete gutter The following materials are: sand cement
1016(1)a	WATERPROOFING (CEMENTITIOUS)	639.16 11.60 236.92 83.40 15.60 200.94 90.70	sq.m.	This covers the following areas in reference from the plans: DECK FLOOR ROOF DECK SECOND FLOOR MULTI-PURPOSE DECK TOP OF PENTHOUSE ROOF SLAB (STAIRS @ GRID F-G) REAR WALL @ GRID A (2-9)-OUTER SIDE ONLY CONCRETE GUTTER The following materials are: Plexibond Cementitious Waterproofing - 2 coats for wall, 3 coats for deck floor/roof deck Paint Roller with pan Cement Paint Brush x 100 Paint Brush x 75
1016(1)a	CEMENT FLOOR TOPPING (Roof deck/Deck floor)	353.30 116.38 236.92	sq.m.	This covers the following areas in reference from the plans: DECK FLOOR ROOF DECK The following materials are: sand cement
1010(2)b	DOORS WOOD PANEL	61.32 3.00 1.00 11.00 4.00	sq.m sets set sets sets	This covers the following doors in reference from the plans: D-5 Panel Door Butterfly with glass tinted (1m x 2.1m) with complete accessories D-6 Panel Door with door jamb (0.90m x 2.1m) with complete accessories D-7 Panel Door with door jamb (0.90m x 2.1m) with complete accessories D-8 Flush Door with door jamb (0.90m x 2.1m) with complete accessories



Republic of the Philippines
KALINGA STATE UNIVERSITY
BIDS AND AWARDS COMMITTEE

National Highway, Purok 6, Bulanao, Tabuk City 3800, Kalinga

Website: <https://ksu.edu.ph> Email: procurementservice_bac@ksu.edu.ph Tel. No.: (074) 627-5321

ITEM No.	ITEMS OF WORK	QTY	UNIT	SCOPE OF WORKS
		4.00	sets	D-9 Flush Door with door jamb (0.80m x 2.1m) with complete accessories
		2.00	sets	D-10 Flush Door with door jamb (0.70m x 2.1m) with complete accessories
		12.00	sets	D-11 Cubicle Door with door jamb (0.60m x 1.3m) with complete accessories
		1.00	set	D-12 Flush Door with door jamb (0.90m x 1.8m) with complete accessories
		1.00	set	D-13 Flush Door with door jamb (0.70m x 1.8m) with complete accessories
		2.00	sets	D-14 Flush Door with door jamb (0.80m x 1.80m) with complete accessories
1008(1)a	ALUMINUM GLASS WINDOW (Sliding Type)	39.67	sq.m	This covers the following windows in reference from the plans:
		2.00	sets	(3.50mx1.50m) Analoc window glass on aluminum frame with 6mm thick glass
		2.00	sets	(2.55mx1.20m) Analoc window glass on aluminum frame with 6mm thick glass
		2.00	sets	(2.05mx1.50m) Analoc window glass on aluminum frame with 6mm thick glass
		3.00	sets	(1.55mx1.20m) Analoc window glass on aluminum frame with 6mm thick glass
		1.00	set	(5.55mx1.80m) Analoc window glass on aluminum frame with 6mm thick glass
1008(1)c	ALUMINUM GLASS WINDOW (Awning Type)	0.20	sq.m	This covers the window in reference from the plans:
		1.00	set	(0.5mx0.4m) Analoc window glass on aluminum frame with 6mm thick glass
1032(1)a	PAINTING MASONRY/ CONCRETE	6487.81	sq.m	This covers the following areas in reference from the plans:
		5,272.16		All Plastered Exterior and Interior Walls (except the Interior Auditorium)
		715.64		Ground floor slabs (soffit) of the following areas
				Props & Scenery Room
				Performers Lobby
				Costume dressing room
				CR
				She, He and PWD
				Utility Room
				Stair at utility room
				Grid 4&7(F-G) & 5&6(G-I)
				Arts production
				Building Maintenance
				Registration
				CR & Security
				Corridor
				Grid CD (3-4)
				Reception Counter
		500.01		Second floor under slabs (soffit) of the following areas
				Under Bleacher
				Grid H'I (4-7)
				Concrete moulding
				stair
				Corridor
				The following materials are:
				Flat white Latex (1st Coat)



Republic of the Philippines
KALINGA STATE UNIVERSITY
BIDS AND AWARDS COMMITTEE

National Highway, Purok 6, Bulanao, Tabuk City 3800, Kalinga

Website: <https://ksu.edu.ph> Email: procurementservice_bac@ksu.edu.ph Tel. No.: (074) 627-5321

ITEM No.	ITEMS OF WORK	QTY	UNIT	SCOPE OF WORKS
				Final Paint (2nd coat and 3rd coat-for exterior wall: ROS Mint Green, ROS Bright Green, ROS Bridal Gown & ROS Brown; for interior wall: ROS Neutral Gray, ROS Stone Gray, ROS Bridal Gown & Black)
				Masonry Neutralizer
				Masonry putty
				Sand paper
				Roller brush with pan
				Paint Brush x 100
				Paint Brush x 75
				Paint Brush x 50
				Roller brush foam
1032(1)b	PAINTING WOOD/ GYPSUM	1338.04	sq.m.	This covers the following areas in reference from the plans:
		1,005.34		Gypsum boards for Ceiling
		179.40		Arts display gallery
		153.30		Wooden Doors
				The following materials are:
				Enamel Flat White
				Enamel Semi-Gloss White
				Sand Paper # 200
				Plasolux Glazing Putty
				Paint Thinner
				Roller Brush Medium Size foam
				Roller Paint Brush M/S with pan
				Paint Brush x 100
				Paint Brush x 75
				Paint Brush x 50
				Enamel Choco Brown
1032(1)c	PAINTING STEEL	429.36	sq.m.	This covers the following steel work in reference from the plans:
		256.56		Metal Railings (stairs, front ramp, corridors, deck floors and others)
		172.80		Architectural Tubing
				The following materials are:
				Quick Dry Enamel Paint (black, white & choco brown)
				Paint Thinner
				Paint Brush x 75
				Paint Brush x 50
SPL I	ALUMINUM GLASS WINDOW GRILLS	33.80	sq.m.	This covers the following windows in reference from the plans:
		2.00	sets	W1(3.50m x 1.50m)
		2.00	sets	W2(2.55m x 1.50m)
		2.00	sets	W3(2.05m x 1.50m)
		5.00	sets	W5(1.55m x 1.20m)
		1.00	set	W8(0.50m x 0.40m)
1007(1)b	ALUMINUM GLASS DOORS	22.26	sq.m.	This covers the following doors in reference from the plans:
		4.00	sets	D-2 Analok swing type door with lockset, 6mm thick (2.1m x 1.6m)
		3.00	sets	D-3 Analok Frame Butterfly glass Door, 6mm thick (2.1m x 1.4m)
1008(1)	ANALOK GLASS PARTITION	67.76	sq.m	This covers the following partitions in reference from the plans:



Republic of the Philippines
KALINGA STATE UNIVERSITY
BIDS AND AWARDS COMMITTEE

National Highway, Purok 6, Bulanao, Tabuk City 3800, Kalinga

Website: <https://ksu.edu.ph> Email: procurementservice_bac@ksu.edu.ph Tel. No.: (074) 627-5321

ITEM No.	ITEMS OF WORK	QTY	UNIT	SCOPE OF WORKS
				Grid 4 & 7(K-M) and Grid M(4-7)
		4.00	sets	(2.60m X 2.80m) Modular Partition Analok Frame S-1000 with 10mm thick Tinted Glass
		4.00	sets	(4.60m X 2.80m) Modular Partition Analok Frame S-1000 with 10mm thick Tinted Glass
401	METAL RAILINGS @	201.45	ln.m	This covers the following areas in reference from the plans:
	stairs, corridors,	38.10		Ground Floor
	balconies, multi-			Grid 3 to (K-N), Grid 3 to (K-N), Grid N to (3-8), Grid 8 to (K-N),
	purpose deck & front			Grid N to (6-7)
	Ramp	125.95		Second Floor
				Grid 4 to (K-M), Grid M to (4-7), Grid 7 to (K-M), Grid F to (4-7),
				Grid K to (4-7), Grid J to (4-5), Grid 3 to (G-H, K-N), Grid N to
				(3-8), Grid 8 to (G-H, K-N), Grid 2 to (A-C), Grid A to (2-4),
				Grid 9 to (A-C), Grid A to (7-9)
		5.00		Third Floor
				Grid J to (5-6)
		32.40		All Stairs (from ground floor to third floor)
				Grid (2-3) to (F-G), Grid (F-G) to (8-9), Grid (I-J) to (4-5)
				The following materials are:
				2mm x 2" x 3" Tubular
				5/8" Round Bar
				1/4" x 1 1/2" Flat Bar
				5/8" Square Bar
				Red Oxide Primer Paint
				Paint Brush 3"
				Welding Rod
1003 (15) b	CONCRETE	192.32	ln.m	This covers the following areas in reference from the plans:
	MOULDINGS	143.70		Parapet Perimeter
				Grid 4 to (A-M) @ 0.40m, Grid 7 to (A-M) @ 0.40m, Grid 5 to
				(M-N) @ 0.40m, Grid 6 to (G-N, K-N) to 3 @ 0.40m, Grid 6 to
				(G-N, K-N) to 8 @ 0.40m, Grid 6 to (3-5, 6-8) to N @ 0.40
		37.52		@ Front & Rear
				Grid M to (4-7), Grid A to (4-7), Grid N to (5-6)
		11.10		@ Arc
				The following materials are:
				cement
				sand
SPL II	STAINLESS LOGO & LETTERINGS	1.00	lot	This covers the following areas in reference from the plans/ specification:
				KSU LOGO-1000mm radius or 2000mm diameter
SPL III	ARCHITECTURAL TUBING "Sun Protector"	39.22	sq.m	This covers the following areas in reference from the plans:
				At Front Elevation
				The following materials are:
				Tubular 1.0mm x 50mm x 75mm
				Tubular 1.5mm x 50mm x 75mm
				Welding Rod
				Red Oxide Primer Paint
				Paint Brush 3"
				Enamel Paint Black
				Expansion Bolt 10mm diam. x 4"
SPL IV	GANG CHAIRS	432.00	pieces	This covers the following areas in reference from the plans:
				216 pieces for Ground Floor Bleacher (ISO type) at Grids D-F



Republic of the Philippines
KALINGA STATE UNIVERSITY
BIDS AND AWARDS COMMITTEE

National Highway, Purok 6, Bulanao, Tabuk City 3800, Kalinga

Website: <https://ksu.edu.ph> Email: procurementservice_bac@ksu.edu.ph Tel. No.: (074) 627-5321

ITEM No.	ITEMS OF WORK	QTY	UNIT	SCOPE OF WORKS
				216 pieces for Second Floor Bleacher (ISO type) at Grids F-I The specifications are: Foldable Stadium Chair (OGD-4151) Size: 770x460x510mm (HxWxD)
1003(2)a1	STAGE OVERHEAD DRY WALL	46.00	sq.m	This covers the following areas in reference from the plans: From Grid C (4-7) The following materials are: Tubular 1.5mm x 50mm x 75mm Welding Rod Primer Paint Paint Brush 3" 4.5mm x 1200mm x 2400mm Fiber Cement Board Gypsum screw x 32 (1000/box)
1031(1)c	ACOUSTIC WALL TREATMENT	580.00	sq.m	This covers the following areas in reference from the plans: All Interior Closed Walls of Auditorium From Grids B-I (4-7) The following materials are: 9mm thick x 4 ft. x 8 ft. Polyester Fiber Acoustic Panel (verify color and design) Liquid Nail Heavy Duty Adhesive
1041(1)	GYPSON BOARD FOR CEILING	1065.75	sq.m	This covers the following areas in reference from the plans: From Grids A-M The following materials are: 9mm thick 4'x8' Gypsum Board Blind rivet x 20mm Metal furring 0.4mm (LMF) x 5m RSB 12mm dia x 6.0 Drop Hangers LMF x 5m Sandpaper No. 100 Sandpaper No. 120 Welding rod 5kg/box "C" Purlin 2mm x 50 x 150 x 6.0 "C" Purlin 2mm x 50 x 100 x 6.1 Gypsum Putty Gypsum screw x 32 (1000/box) * for Shadow Line 3/4" x 4ft x 8ft Ordinary Plywood Metal Wall Angle 0.4mm (LMF) x 5m
1100	CONDUITS, BOXES AND FITTINGS	1.00	L.S	The following materials are: Conduits, 75mm inside diameter-sched. 80, PVC Pipe Conduits, 75mm inside diameter-sched.80, PVC elbow 75mmØ Locknut and adapter
1101	WIRES AND WIRING DEVICES	1.00	L.S	The following materials are: Wire # 2.0mm ² THHN copper stranded 600V (Green) Wire #3.5mm ² THHN copper stranded 600V (Red) Wire #3.5mm ² THHN copper stranded 600V (White) Wire #150mm ² THW copper stranded 600V (Red) Wire #150mm ² THW copper stranded 600V (Blue) Wire #150mm ² THW copper stranded 600V (White) Convenience outlet, 16A, Duplex, 3prong, 250V Electrical Tape



Republic of the Philippines
KALINGA STATE UNIVERSITY
BIDS AND AWARDS COMMITTEE

National Highway, Purok 6, Bulanao, Tabuk City 3800, Kalinga

Website: <https://ksu.edu.ph> Email: procurementservice_bac@ksu.edu.ph Tel. No.: (074) 627-5321

ITEM No.	ITEMS OF WORK	QTY	UNIT	SCOPE OF WORKS
1103	LIGHTING FIXTURES	1.00	L.S	The following materials are: Pinlight 18W LED (RECESSED TYPE) Pinlight 18W LED AMGLOBE 300Ø WITH LED LIGHT ON SINGLE ARM LIGHT POST.
1200 (4) a1	Package type Aircon- ditioning unit PACU (wall mounted inverter)	12.00	sets	The following specifications are: 2 Hp ACU (WINDOW TYPE) with Manual 3 Hp ACU (SPLIT TYPE) with Manual
1102 (10)b	Pole Mounted Trans- former (OISC)	3.00	sets	The following specifications are: 1. 50kVA distribution transformer pole mounted, conventional type, 7620/13200Y primary - 240/480V secondary, single phase oil immersed self-cooled 60hz, all copper windings 95kV BIL, with 2-2.5% taps ANFC and BNFC externally operated tap changer, manufactured in accordance with NEMA and ANSI standards. ISO 9001 certified. double bushing. Brand new. NEA standard losses at 85°C temperature 2. Polymer/Porcelain Fuse cut-out 100 and ohio brass polymer lightning arrester 3. 10amps fuse link 4. Steel cross arm 3"x4"x8' 5. Strain dead-end clamp 1/0 6. Insulator pin-type 55-5 7. Ground rod, steel 5/9 x 10' HDG 8. Grounding clamp 5/8 9. Hotline clamp 10. Grounding wire 3/8 11. Suspension insulator 52-1 12. Steel pin 5/8 13. ACSR #2 14. Guy wire 3/8 15. Anchor expanding 8 ways 16. Anchor rod single eye 5/8 x 7' 17. Machine Bolt 5/8" x 6" 18. oval Bolt 5/8" x 8" 19. 3 bolt clamp HDG
1018(7)	GLAZED TILES	1541.85	sq.m.	This covers the following areas in reference from the plans: All interior areas excluding ramps and decks The following materials are: Granite Tiles Glazed (600 x 600mm) - Supreme White and Super Gray (or approved equal) Portland Cement Sand Bostik Tile Grout Fix All Tile Cutter Disk Brass nosing x 3.0 m
1018(2)	UNGLAZED TILES	459.26	sq.m.	This covers the following areas in reference from the plans: All exterior areas including ramps and decks The following materials are: Granite Tiles Unglazed (600 x 600mm) Dark Gray and Light Gray Color Tactile Tiles (13mm thick x 300x300mm) Dark Gray Color Portland Cement



Republic of the Philippines
KALINGA STATE UNIVERSITY
BIDS AND AWARDS COMMITTEE

National Highway, Purok 6, Bulanao, Tabuk City 3800, Kalinga

Website: <https://ksu.edu.ph> Email: procurementservice_bac@ksu.edu.ph Tel. No.: (074) 627-5321

ITEM No.	ITEMS OF WORK	QTY	UNIT	SCOPE OF WORKS
				Sand
				Bostik Tile Grout Fix All
1002(8)	PLUMBING FIXTURES	1.00	L.S.	This covers the following areas in reference from the plans: Deficiencies from previous phase
				The following materials are:
				1. Water Closet assembly (water closet with tank), including fittings & accessories (round) American std or equal Assy.
				2. Lavatory Assy. (big) with faucet, including fittings and accessories
				3. Floor Drain 100 x 100, stainless
1003(13)	PHENOLIC BOARD (URINAL DIVIDER)	4.00	pcs	This covers the following areas in reference from the plans: For toilets
				The following materials are:
				Phenolic Board (3/4" thick x 400mm x 900mm) with complete mounting accessories-wood like design
1001(1)a8	SEWER LINE	1.00	L.S.	This covers the following areas in reference from the plans: Refer to sewer line layout
				The following materials are:
				1. PVC Pipe 150 dia x 3.0m series 1000
				2. PVC solvent cement 500 cc
1001	ROOF LEADER/ DOWNSPOUT DRAIN	1.00	L.S.	This covers the following areas in reference from the plans: Refer to layout
				The following materials are:
				1. PVC pipe 100 dia x 3.0m sc 40
				2. PVC elbow 100 dia x 90 deg
				3. PVC coupling 100 dia
				4. PVC clamp, flat bar 4mm x 25 x 300
				5. Tokscrew x 25mm
				6. Concrete drill bit
				7. PVC wye x 100 dia
				8. PVC elbow 100 dia x 45deg
				9. Solvent cement 400 cc
				10. Brass dome shape downspout strainer x 100
				11. Brass floor strainer 100 dia
1006(3)	GRILL COVER (for storm drainage line)	33.60	kgs.	This covers the following areas in reference from the plans: Refer to layout
				The following materials are:
				1. Angle bar 6mm x 25 x 25 x 6.0
				2. RSB 10mm dia x 6.0
				3. Welding Rod
				4. Hacksaw blade
				5. Epoxy primer paint gray/pair
				6. Paint brush x 50
1107	PUBLIC ADDRESS SYSTEM	1.00	L.S.	The following specifications are:
				1. Powered Audio Mixer - 12 inputs (Peavey) or similar brand stereo 1000 watts per channel
				2. Power Audio Amplifier (Peavey-CS4080) or similar brand stereo
				3. Electro Voice Ceiling Mounted Speaker (300 Watts - 2-way Speaker)
				4. Speaker Set 3-way speaker 100 watts (consul type) 15" woofer



Republic of the Philippines
KALINGA STATE UNIVERSITY
BIDS AND AWARDS COMMITTEE
National Highway, Purok 6, Bulanao, Tabuk City 3800, Kalinga

Website: <https://ksu.edu.ph> Email: procurementservice_bac@ksu.edu.ph Tel. No.: (074) 627-5321

ITEM No.	ITEMS OF WORK	QTY	UNIT	SCOPE OF WORKS
				5. Microphone Stand boom type
				6. Wireless microphone with 4 microphone (Pevey) or similar brand
				7. Microphone with chord (Peavey or Shure)
				8. Speaker Cable # 14 or # 16
				9. Speak on connectors (male)
				10. Speak on connectors (Female-surface mounted)
				11. Microphone cable (balanced type) Heavy duty
				12. XLR Connector (Male)
				13. XLR Connector (Female)
				14. XLR Connector (Male surfaced mounted)
				15. XLR Connector (Female surfaced mounted)
				16. Soldering Lead 60/40
				17. Soldering Pen 40Watt
				18. Electrical Tape (big)
				19. Microphone Plug (Mono)
SPL VI	MISCELLANEOUS WORKS	1.00	Ls	The following material is: Fire Extinguishers (Red)
B.7	OCCUPATIONAL SAFETY AND HEALTH PROGRAM	1.00	lot	The following equipment/materials are: safety gloves safety shoes safety helmets
SPL V	PROJECT BILLBOARD	1.00	piece	The following materials are: 1/4" x 4' x 8' marine plywood good lumber tarpaulin (4' x 8') CWN (assorted)

15
16
17
18
19
20
21

PARTICULARS	CLARIFICATION / AMENDMENT
On Section VIII- Bill of Quantities, pages 83-85 of the bid document, the following is the Revised BOQ:	

ITEM NO.	DESCRIPTION	QTY	UNIT	Unit Price (in Pesos)	Total Cost (in Pesos)
1046(2)a1	100 mm CHB Non-Load Bearing Wall (including Reinforcing Steel)	640.50	sq.m.		
404	REINFORCING STEEL BARS	272.70	kgs		
900	CONCRETE WORKS	3.59	cu.m		
903(2)	FORMS AND FALSEWORKS	20.96	sq.m		
1027(1)	PLAIN CEMENT PLASTER FINISH	3,438.59	sq.m.		
1016(1)a	WATERPROOFING (CEMENTITIOUS)	639.16	sq.m.		
1021(3)a	CEMENT FLOOR TOPPING (Roof deck/Deck floor)	353.30	sq.m.		
1010(2)b	DOORS WOOD PANEL	61.32	sq.m		
1008(1)a	ALUMINUM GLASS WINDOW (Sliding Type)	39.67	sq.m		
1008(1)c	ALUMINUM GLASS WINDOW (Awning Type)	0.20	sq.m		
1032(1)a	PAINTING MASONRY/CONCRETE	6,487.81	sq.m		
1032(1)b	PAINTING WOOD/GYPSUM	1,338.04	sq.m.		
1032(1)c	PAINTING STEEL	429.36	sq.m.		
SPL I	ALUMINUM GLASS WINDOW GRILLS	33.80	sq.m.		
1007(1)b	ALUMINUM GLASS DOORS	22.26	sq.m.		
1008(1)	ANALOK GLASS PARTITION	67.76	sq.m		



Republic of the Philippines
KALINGA STATE UNIVERSITY
BIDS AND AWARDS COMMITTEE
 National Highway, Purok 6, Bulanao, Tabuk City 3800, Kalinga

Website: <https://ksu.edu.ph> Email: procurementservice_bac@ksu.edu.ph Tel. No.: (074) 627-5321

401	METAL RAILINGS @ stairs, corridors, balconies, multi-purpose deck & front Ramp	201.45	ln.m		
1003 (15) b	CONCRETE MOULDINGS	192.32	ln.m		
SPL II	STAINLESS LOGO & LETTERINGS	1.00	lot		
SPL III	ARCHITECTURAL TUBING "Sun Protector"	39.22	sq.m		
SPL IV	GANG CHAIRS	432.00	pieces		
1003(2)a1	STAGE OVERHEAD DRY WALL	46.00	sq.m		
1031(1)c	ACOUSTIC WALL TREATMENT	580.30	sq.m		
1041(1)	GYPSUM BOARD FOR CEILING	1,065.75	sq.m		
1100	CONDUITS, BOXES AND FITTINGS	1.00	l.s		
1101	WIRES AND WIRING DEVICES	1.00	l.s		
1103	LIGHTING FIXTURES	1.00	l.s		
1200 (4) a1	Package type Airconditioning unit PACU (wall mounted inverter)	12.00	sets		
1102 (10)b	Pole Mounted Transformer (OISC)	3.00	sets		
1018(7)	GLAZED TILES	1,541.85	sq.m.		
1018(2)	UNGLAZED TILES	459.26	sq.m.		
1002(8)	PLUMBING FIXTURES	1.00	l.s		
1003(13)	PHENOLIC BOARD (URINAL DIVIDER)	4.00	piece		
1001(1)a8	SEWER LINE	1.00	l.s		
1001	ROOF LEADER/DOWNSPOUT DRAIN	1.00	l.s		
1006(3)	GRILL COVER (for storm drainage line)	33.60	kgs.		
1107	PUBLIC ADDRESS SYSTEM	1.00	l.s		
SPL VI	MISCELLANEOUS WORKS	1.00	Ls		
B.7	OCCUPATIONAL SAFETY AND HEALTH PROGRAM	1.00	lot		
SPL V	PROJECT BILLBOARD	1.00	piece		
				TOTAL BID AMOUNT (in figures): Php	
				TOTAL BID AMOUNT (in words): Pesos	

22
23
24
25
26
27
28
29
30
31
32
33
34
35
36
37
38
39
40
41
42
43
44
45
46
47
48
49
50

PARTICULARS	CLARIFICATION / AMENDMENT
<p>The new Contract Duration is revised from Three Hundred Ten (310) into Three Hundred Six (306) Calendar Days and the following parts of bid documents shall be affected:</p> <ol style="list-style-type: none"> 1. 2nd Paragraph of the Invitation to Bid; 2. ITB Clause 1.2 of the Bid Data Sheet; 3. GCC Clause 1.17 of the Special Conditions of Contract; 4. Number 3.5 of Letter III of the Terms of Reference under Section VI- Specifications; and 5. Notation on Project Duration after the Bill of Quantities at Section VIII- BOQ. 	

For guidance and information of all concerned.


 EDNA P. YUMOL, CPA, PhD
 BAC Chairperson 

Date Issued: October 29, 2019
 Copy furnished: Prospective Bidders